TABLE OF CONTENTS

Pages

NOTICE TO SUPPLIERS....1

INSTRUCTIONS TO BIDDERS....8

GENERAL CONDITIONS....9

SPECIAL CONDITIONS....4

BID PROPOSAL INSTRUCTIONS....2

PRICE PROPOSAL FORM....5

TECHNICAL SPECIFICATIONS....40

BID FORM....2

- BIDDER'S QUALIFICATIONS & REFERENCES FORM....4
- CLERK'S CERTIFICATE....1
- ATTESTATION CLAUSE FORM....1
- CERTIFICATE OF NON-COLLUSION....1
- PUBLIC CONTRACTS – DEBARMENT....1
- CONFLICT OF INTEREST CERTIFICATION....1
- FORM W-9....6

DRAWINGS (PROVIDED FOR REFERENCE ONLY)

- FIRST FLOOR PLAN – HEADQUARTERS
- SECOND FLOOR PLAN – HEADQUARTERS
- FLOOR PLANS – SUPPORT BUILDING

NOTICE TO SUPPLIERS

The City of Woburn, the Awarding Authority, invites sealed bids for Furnishings and Equipment for the Woburn Fire Headquarters, Woburn, MA in accordance with the Contract Documents prepared by DiNisco Design, Inc., 99 Chauncy St., Boston, Massachusetts, 02111.

Contract Completion: 21 OCTOBER 2022. DELIVERY AND INSTALLATION FOR THIS PROJECT IS CRITICAL SINCE THE CONTRACT COMPLETION WINDOW OCCURS PRIOR TO THE BUILDING OPENING. VENDORS UNABLE TO ABIDE BY THIS SCHEDULE NEED NOT BID.

Bids shall be submitted on a form furnished by the Awarding Authority, sealed in an opaque envelope marked with the bidder's name, address, and section numbers bid, and shall be filed with the Awarding Authority prior to **11:00 AM Thursday, 14 April 2022** when they shall be publicly opened andread aloud. Any bid received after the time and date specified will not be considered.

Bids shall be addressed as follows:

City of Woburn – Town Hall
Purchasing Department
10 Common Street
Woburn, MA 01801

Attn: Orazio DeLuca
Chief Procurement Officer
Woburn Fire Headquarters FFE Bids

All Bid Forms must be submitted in duplicate. Refer to "Instructions to Bidders."

Bid documents are available in electronic form ONLY. To request documents, email m.hestand@dinisco.com, referencing Woburn Fire Headquarters FFE Bid.

Every bid shall be accompanied by a bid deposit in the form of a bid bond, cash or a certified check, or a treasurer's or cashier's check issued by a responsible bank or trust company, payableto the City of Woburn. The amount of such bid deposit shall be 5% of the total bid. The Awarding Authority reserves the right to reject any or all bids if it deems in its sole discretion to be in the public interest to do so. All bids are subject to the provision of M.G.L. c.30B, the Uniform Procurement Act. All bids submitted and opened must remain fixed and in force, as submitted, for 90 days (Saturdays, Sundays and legal holidays excluded) following the openings of bids, or until such later time as may be required by law.

Orazio DeLuca
Chief Procurement Officer
City of Woburn

24 MARCH 2022

INSTRUCTIONS TO BIDDERS

1. PREPARATION AND SUBMISSION OF BIDS

1.1 Bids shall be submitted on the “Bid Forms” contained herein.

1.2 All entries on the Bid Forms shall be made by typewriter or in ink.

1.3 Where so indicated on the Bid Form, sums shall be expressed in both words and figures. Where there is a discrepancy between the bid sum expressed in words and the bid sum expressed in figures, the words shall control.

1.4 Any bid received after the time and date specified will not be considered. The bid shall be enclosed in an opaque sealed envelope with the following plainly marked on the outside:

NAME OF PROJECT: **Supply and Deliver Furnishings and Equipment for the Woburn Fire Headquarters**

BIDDER’S NAME, BIDDER’S ADDRESS AND PHONE NUMBER

BID OPENING DATE: THURSDAY, 04/14/2022 @ 11:00 AM

1.5 Bids shall be delivered to:

City of Woburn Purchasing Department
Woburn, MA 01801

1.6 Every bid shall be accompanied by a bid deposit in the form of a bid bond, cash or a certified check, or a treasurer's or cashier's check issued by a responsible bank or trust company, payable to the City of Woburn, MA. The amount of such bid deposit shall be 5% of the total bid.

1.7 Each bidder must sign and submit with its Bid, forms certifying that they are in compliance with all requirements of MGL c. 268A (Conduct of Public Officials and Employees) at time the awarding of contract.

1.8 The City reserves the right to vary quantities, to reject any/or all Bids, or any part of any Bid if it deems in its sole discretion to be in the public interest to do so. The City will reject any and all bids in accordance with the above referenced General Laws. In addition, the City reserves the right to waive minor informalities in any or all bids, or to reject any or all bids (in whole or in part) if it be in the public interest to do so.

2. PROVISIONS OF LAW

2.1 All proposals submitted shall be subject to all applicable provisions of law, including specifically but without limiting the generality of the foregoing, Chapter 30B, as amended, of the General Laws.

3. EXAMINATION OF DOCUMENTS AND SITE

3.1 Before submitting his proposal, each Bidder shall carefully examine the bid documents, visit the site and thoroughly familiarize himself with the existing conditions relating to construction and labor. Failure to do so will not relieve the bidder from any obligation under his bid as submitted. By submitting a bid, the Bidder agrees and assures that the site, the plans, and the specifications have been examined; that the plans and specification are adequate; and that the required results can be produced under those plans and specifications.

4. INTERPRETATION AND ADDENDA

4.1 All questions as to the interpretation of the bid documents, including but not limited to the plans and specifications shall be submitted in writing via email to the Architect, DiNisco Design, attn: Mallory Hestand, m.hestand@dinisco.com; referencing the Woburn Fire Headquarters Furniture and Equipment Bid.

4.2 The Architect will answer any such questions requiring interpretation of the bid documents, if received not later than April 10, 2022 at 12:00 NOON by issuing addenda to the specifications. It shall be the Bidder's responsibility for checking the issuing website for any addenda. Such addenda will become part of the Contract Documents. Neither the City of Woburn nor the Architect will be responsible for any oral communication.

4.3 Failure of any Bidder to obtain such addenda will not relieve any Bidder from any obligation under his bid as submitted.

4.4 Any Addenda forming a part of the plans and specifications, or issued before the opening of bids, shall be covered in the bid and shall be a part of the Contract.

5. REQUIREMENTS FOR "FOREIGN CORPORATIONS"

5.1 By submitting a bid, the Bidder agrees if it is a foreign corporation and its bid is accepted, to comply with the requirements of Sections 3 and 5 of Chapter 181 of the Massachusetts General Laws, before the time for execution of the Contract occurs. The term "foreign corporation" means a corporation not incorporated under the laws of the Commonwealth of Massachusetts.

6. GENERAL SCOPE OF WORK

6.1 Unless otherwise specifically specified to be assembled / installed by the Owner, all items in the plans and specifications shall be furnished and installed, set in place upon delivery as directed by the City of Woburn or its representative or as indicated on drawings, bolted or otherwise fastened if required, and, after connection of services by the building General Contractor, made fully and perfectly operative.

7. EXPLANATION OF REQUIREMENTS IN TECHNICAL SECTIONS

7.1 Bidders shall refer to the number coded items in the Technical Specifications, designed to provide each Bidder with a clear understanding of the requirements he must meet. These serve to establish specifically the standard of quality, function and performance of the items to be furnished, and do this by referring to representative manufacturers and detailed specifications. These shall be used as a basis of design in the evaluation of any proposed alternates, see paragraph 12. SAMPLES.

7.2 The intent of the Bid Documents is to secure a range of furnishings, necessarily obtained from different suppliers and composed of the work of many different manufacturers, which harmonize not only in function and dimension, but also in appearance. The prime method for obtaining this harmony is through the use of color and finishes. Therefore, as part of the general design, all items, whether named or bid as alternatives, must comply with the overall requirement of color harmony. All color and finish within any single technical section may be required to match exactly. Color and finish on items to be located in adjacent spaces or within the same space may be required to match exactly, if so indicated in their respective color and finish description. In general, the Architect will require reasonable compliance by all bidders to the stated colors and in so doing will not necessarily be bound by any so-called "standard" or "special" color lists in satisfaction of this requirement. Any bidder seeking to furnish an item not embodying the exact color or finish specified in the Documents must submit their proposed color range to the Architect for approval under paragraph 12, SAMPLES. Any item for which colors have not been so submitted and approved will be assumed by the Architect to be supplied in the specified colors and finishes.

7.3 Special Requirements or product modifications may appear in any technical section for which specific requirements or added information is required; when present in such a section, the Bidder will be held to conformance therein.

7.4 The Item Code designations in the specifications and on the plans are provided as an aid to successful bidders.

8. PREPARATION OF BIDS

8.1 Bids shall be submitted in duplicate on the Bid Proposal Form enclosed separately with the Bid Documents. Each Bidder shall indicate the extent of work upon which he wishes to propose by entering his bid prices in the appropriate spaces on the Bid Proposal. Make no marks adjacent to items upon which no bid is proposed. Excepting these specifically described spaces, the Bid Proposal Form shall be completely filled in and signed. Bids which are incomplete, conditional or obscure, or which contain additions not called for, will be rejected.

8.2 Bids shall be for the complete work of one or more number coded items in one or more Furnishings/Equipment categories. Each Bidder must supply all pricing and identify all proposed items in the space provided for each item that he bids; it is the sole responsibility of the Bidder to completely identify the items upon which his bid is based.

8.3 Each Bidder shall retain one copy of bid documents for his records and file two (2) Bid Proposal Forms, complete with supporting literature with the City of Woburn at the place designated in the Notice to Suppliers. The bid shall be filed before the deadline designated in the Invitation to Bid. The bid must include the following documents:

i. Bid Proposal completed and signed with unit cost and total cost of each item bid. If an Alternate is bid, proposal must provide alternate's Manufacturer/Model Number along with supporting document as indicated in 7.3.10 and 12. SAMPLES.

ii. Clerk's Certificate – completed and signed.

iii. Attestation Clause form – completed and signed.

iv. Certificate of Non-Collusion – completed and signed.

v. Public Contracts – Debarment – completed and signed.

vi. Conflict of Interest Certificate – completed and signed.

vii. W-9 – completed and signed.

viii. References – as indicated in Paragraph 15, Invitation to Bid/Instructions to Bidders.

ix. Bid Deposit – as indicated in Paragraph 9, Invitation to Bid/Instructions to Bidders.

x. Provide for each proposed Alternate manufacturer's catalog cuts. Include on each document the reference code number (i.e. 01.CH.0018) for proposed Alternate, highlighting the exact manufacturer correlating model number, color/finish and or available colors/finishes. Also provide information that illustrates the conformity of the proposed alternate to the specification.

8.4 Each bid proposal shall be as instructed per Article 1.4. The sealed envelope shall be enclosed in an outer-seal envelope and delivered to the address indicated in the INSTRUCTIONS TO BIDDERS. If bids are forwarded by mail, they must be registered or certified. Any bid received after the scheduled closing time for the receipt of bids as established in the INSTRUCTION TO BIDDERS shall be returned to the Bidder unopened.

9. MODIFICATION AND WITHDRAWAL OF BIDS

9.1 A bid may be modified or withdrawn by written notice received in the office designated in the Notice to Suppliers for submission of bids, provided that such request is received prior to the time and date established in the Notice to Suppliers for the bid opening. Modifications shall be sealed and marked in the same format applicable to bids. The City of Woburn will not be responsible, however, for the timely receipt of any request for modification or withdrawal, and Bidders are cautioned to transmit any such request for modification or withdrawal in ample time for delivery before the Bid Opening time.

9.2 No bidder may modify or withdraw his proposal after the actual opening thereof without the written permission of the City of Woburn, which shall be granted only pursuant to M.G.L. Chapter 30B.

10. BID DEPOSIT

10.1 Each Bid Proposal shall be accompanied by a Bid Deposit in the form of cash, a certified check, a treasurer's check or cashier's check, or a bid bond issued by a responsible surety company licensed by the State Division of Insurance, payable to the City of Woburn in the amount of five percent (5%) of the total bid amount. Said Bid Deposit shall become and be the property of the City of Woburn as liquidated damages if, after an award is made to him, the Bidder shall fail to enter into the required contract within five (5) working days after notice of said award is mailed or delivered to him.

10.2 Bidder's submitting cash, certified check or treasurer's check as a Bid Deposit shall, if successful, have their Bid Deposit retained by the City of Woburn until such time that the contractual obligations of the successful Bidder have been completed.

10.3 All Bid Deposits of successful bidders will be returned not later than ten (10) working days upon execution and delivery of the contract for the proposed work, or, if no award is made, not later than upon the expiration of ninety (90) working days following the opening of Bids.

11. PERFORMANCE AND PAYMENT BONDS

11.1 Not Required

12. SAMPLES

12.1 Samples may be required from any bidder proposing an item other than the item specified in the Bid Documents. Each Bidder proposing such an alternate shall be prepared to submit samples of all alternate items on which his proposal has been based, within five (5) days, Saturdays, Sundays and legal holidays excluded, after receipt of bid from the Architect. To facilitate comparison and evaluation of alternates, the Architect may also request an example of the item named as a reference in the specification. Failure to provide samples as described herein within the time required will result in award to next lowest bidder.

12.2 Alternate items to those actually named or specified in the Bid Documents will be considered for approval as equals by the Architect only upon receipt of the following by the Architect at the location and within the time period designated by the Architect:

i. One (1) truly representative sample of each item requested by the Architect, complete in every respect, with regard to materials, gauges, thickness, finishes, and construction. No future compliance assertions to the Bid Documents, or "can do" provisions, made by the Bidder, will be accepted as consideration for approval as an equal, without specific written approval of the Architect and City of Woburn.

Note: Technical Specifications and drawings indicating details of construction, catalog descriptions and brochures may not be accepted as sole compliance with this requirement.

ii. Samples of the actual color and finishes as required under each Section integrally a part of, or applied to, the actual materials proposed for use under this Contract.

iii. Manufacturer's printed methods and materials recommended for the cleaning and maintenance of each surface. A list of forbidden practices and typical cleaning agents which would cause manufacturer to request voiding of the guarantee.

12.3 All samples must be securely labeled with the name of the project and the following items:

Code number and name of Section of Specifications

Manufacturer's Name(s)

Name, address and telephone number of the submitting bidder

12.4 All charges in connection with the delivery and retrieval of samples shall be borne by the respective potential bidders.

12.5 The materials and/or equipment furnished under the Contact shall in all respects be equal in quality the samples submitted to and approved by the Architect and/or City of Woburn.

12.6 If requested by vendor, samples will be returned if costs to return are prepaid by vendor.

13. SALES TAX EXEMPTION

13.1 All material and equipment which will be incorporated into the project, and which will become the property of the City of Woburn upon completion of said project, will be exempt from the Massachusetts Sales Tax. The Contractor shall obtain from the City of Woburn the Sales Tax Exemption Number applicable for the project, and shall include said number when ordering materials for the project.

14. AWARD OF CONTRACT AND QUANTITIES

14.1 The Contract will be awarded to the lowest responsible and responsive bidder on the basis of the proposed Contract Price for each item or complete section of the specifications. The City of Woburn may award contracts based on either individual or based on various items included in a section if it in the public interest to do so. Accordingly, the City of Woburn may award one contract or as many contracts as there are bidders. Bidders may at their option submit bids on any or all individual items and may also submit bids for sections provided that any bidder bidding sections must also submit individual line item bids for all items included in such sections.

14.2 As used herein, the term "lowest responsible and responsive bidder" shall mean the Bidder whose Bid is the lowest of those Bidders possessing the capability to perform fully the contract requirements, and the integrity and reliability which assures good faith performance, and who has submitted a bid which conforms in all respects to the invitation for bids and instructions to bidders. The City of Woburn may require information in regard to such qualifications in such form, as it shall deem necessary.

14.3 Quantities established in the specification are estimates, and the City of Woburn reserves the privilege of increasing or decreasing the quantities of individual items within any Section and varying their relative proportions thereby. Such increases or decreases shall not be greater than ten percent (10%) of the listed amounts. City of Woburn may choose to not award any contract for individual items.

14.4 The City of Woburn may award contracts based on either individual items or based on various items included in a section if it is in the public interest to do so.

14.5 An Award Recommendation, indicating all awarded items, quantities and cost will be issued to each successful bidder. If any bidder selected as the supplier for any item(s) or section(s) fails to sign and return this Award Recommendation within five (5) working days after being furnished by the City of Woburn, an award may be made to the next lowest responsible and responsive bidder, and the bidder failing to perform shall forfeit his bid deposit.

14.6 Bids submitted and opened must remain fixed and in force, as submitted, for ninety (90) days (Saturdays, Sundays and legal holidays excluded) following the opening of bids, or until such later time as may be required by law.

15. REJECTION OF BIDS

15.1 The City of Woburn reserves the right to reject any or all bids if it deems it in its sole discretion to be in the public interest to do so, and to waive minor informalities or allow bidder to correct them, all in accordance with the provisions of M.G.L. Chapter 30B.

END OF SECTION

GENERAL CONDITIONS

1. THE OWNER

1.1. The Owner, also referred to as the City of Woburn, MA as represented by and acting through the Purchasing Department.

2. THE ARCHITECT

2.1. The Architect, DiNisco Design, Inc., 99 Chauncy St., Ste 901, Boston, MA 02111 shall be the representative of the Owner during the Contract period and shall observe the work in progress on behalf of the Owner. He shall be the interpreter of the Contract Documents; he shall have the authority to reject non-conforming work. Along with the Owner's Project Manager, the Architect shall evaluate the Contractor's applications for payment and make recommendations to the Owner and confirm the date of final completion of the work.

3. THE CONTRACTOR

3.1. The Contractor is the individual owner, partnership, or corporation including all authorized representatives of such mentioned in the Contract, performing the work as described in the Contract.

3.2. The Contractor shall furnish all material, labor, equipment, supplies, plants, tools, transportation, cartage of every description, superintendent, insurance, taxes, licenses and fees, installation of FURNISHINGS AND EQUIPMENT, and other services necessary for compliance with the Contract Documents

3.3. The Contractor shall obtain and pay for all permits and licenses of a temporary nature necessary for the performance of supplying, delivery and installation of furnishings and equipment.

3.4. The Contractor shall give all notices and comply with all laws, ordinances, rules and regulations relating to the conduct of the work as planned and specified.

3.5. If the Contractor observes that the Drawings and Specifications are ambiguous or at variance with each other, he shall promptly notify the Architect.

3.6. The Contractor shall furnish such bonds as are called for in the Invitation to Bid and Instructions to Bidders.

3.7. Before executing contract work, the Contractor shall furnish to the Owner satisfactory proof that he has taken out and is maintaining all the insurance required hereunder.

3.8. The Contractor agrees that he is fully responsible to the Owner for the acts and omissions of his Subcontractors, if any, and of persons employed by them, as he is for the acts and omissions of persons employed by him.

4. SEPARATE CONTRACTS/COORDINATION WITH SCHOOL OPERATIONS

4.1. If any part of the Contractor's work depends for proper execution or result upon the work of any other contractor, the Contractor shall inspect and promptly report to the Owner any defects in such work that renders it unsuitable for such proper execution and results. Failure to so inspect and report shall constitute acceptance of the other contractor's work except where defects develop in the other contractor's work after the execution of the Contractor's work. The Contractor shall coordinate his work and cooperate with other contractors.

5. PROTECTION OF WORK AND PROPERTY

5.1. The Contractor shall bear all risks of loss or of damage to all material, moveable furnishings and equipment to be provided by him hereunder until delivered to the appropriate building and placed in designated areas, unless otherwise agreed to by the Owner in writing.

5.2. The Contractor shall take all proper precautions to protect persons and existing property from injury, unnecessary interference or inconvenience and shall be responsible for the results of any failure in doing so.

5.3. The Contractor shall bear entire responsibility for the proper layout of his work and any damage, which he may cause to occur by any act or omission on his part.

5.4. The Contractor shall protect any staging area where they are assembling with 6 mil. poly and ¼” Masonite or other alternative protective materials as approved by the Owner.

5.5. The Contractor shall provide protection around door/elevator openings and elevator cab (if not provided by others) to prevent damage while transporting/installing furnishings and equipment.

6. TIME

6.1. All time limits stated in the Contract Documents are of the essence to the Contract.

6.2. If the Contractor is delayed in the prosecution or completion of the work by any damage caused by fire, war, embargoes, Acts of God, general strikes or lock-outs caused by acts of employees, adverse weather conditions not reasonably anticipated, or by delay caused by the Owner or the other contractors hired by the Owner, or other casualty for which the Contractor is not responsible, he shall be allowed such extension of time with no increase in price, for completion of the work. The Owner shall determine to be just. No extension of time for the completion of the work for any cause mentioned in this article shall be made unless a claim for extension of time is presented, in writing, to the Owner within seventy-two hours of the occurrence of such cause. Such extension of contract time shall be the Contractor's sole remedy in the event of delay.

7. REIMBURSEMENT TO THE OWNER FOR LOSS

7.1. If the Contractor delays the progress of any work let by the Owner under a separate contract, apart from this Contract, so as to cause loss for which the Owner becomes liable, then he shall reimburse the Owner for such loss, in such sums as the Owner shall determine to be just.

8. GUARANTEE

8.1. In consideration of the execution of this Contract by the Owner and the price herein stipulated to be paid and received for the work, the Contractor hereby binds and obligates himself and does hereby agree to bring all portions of the work under this Contract to entire completion free of all defects of material or workmanship and guarantees that the said work shall remain free of all defects of material and workmanship for a period of one (1) year from the date of final payment for the work, and also guarantees on written notice from the Owner to forthwith repair, and make good or cause to be repaired and made good, at his own expense and to the satisfaction of the Owner, all defects of material or workmanship in the said work and to pay for or cause to be paid for any damage to other work resulting therefrom, which may develop during the period of one (1) year from the date of final payment for the work under this Contract. The establishment of the time period of one year in this Section 8 relates only to the specific obligation of the Contractor to correct the work, and shall not supersede the terms of any warranty required by the Contract Documents. Longer manufacturer’s warranties shall be passed on to the Owner.

9. COPIES OF DOCUMENTS FURNISHED

9.1. The Architect will furnish, free of charge, one complete set of electronic Drawings and Specifications to the contractor for the execution of the work.

10. EXAMINATION OF PREMISES AND CONDITIONS AFFECTING THE WORK

10.1. It is agreed and understood that the Contractor has examined the premises and is satisfied as to the existing conditions under which he will be obliged to operate in performing the work.

10.2. The Contractor shall not enter or have access to any space in the building in order to perform the work without first having given timely notice to the Owner so that the necessary arrangements may be made. In the performance of the work, the Contractor shall at all times furnish and maintain proper protection for the floors, walls, ceilings, fixtures, equipment, furniture, and/or other property of the Owner.

10.3. There shall be no idling of Contractor vehicles while onsite or in the adjacent neighborhood.

11. OBTAINING AND STUDY OF INSTRUCTIONS

11.1. The Contractor shall carefully study all specifications, drawings and other instructions from the Owner as they are delivered, and procure from the Owner or the Architect such special information, detailed drawings, etc., as may be necessary for the proper performance of the work.

12. QUALITY OF THE WORK

12.1. The Contractor shall carry out the work with due diligence and dispatch. All work performed and materials furnished shall be new and of the best quality and workmanship and to the satisfaction of the Architect and the Owner and shall be in strict accordance with the Contract requirements. Reused or refurbished items will not be accepted.

13. MATERIALS

13.1. All materials shall be new and delivered in manufacturer's original containers, clearly marked as to contents.

13.2. All materials shall be handled, installed and protected in accordance with the best practice in the industry and in strict accordance with the manufacturer's specifications and directions, except as the Contractor may be otherwise directed by the Owner or the Architect acting pursuant to the provisions of the Contract.

14. SUPERVISION

14.1. The Contractor shall provide a FULL TIME person for on-site supervision, during the performance of any trade work associated with this contract. This individual and his qualifications shall be subject to the approval of the Owner.

15. CLEANING UP

15.1. Immediately after unpacking materials, the Contractor shall collect and remove from the site/premises all packing case lumber or other materials, excelsior, wrappings and other rubbish caused by his operations. Under no circumstances shall the Contractor use any on-site dumpster or dumping facility without prior written permission of the Owner.

15.2. At the completion of his work, the Contractor shall leave the work area "broom clean."

15.3. All materials, hardware, fixtures, and other equipment shall be left in undamaged, bright, polished condition.

15.4. All finished surfaces shall be left in perfect condition free of stains, spots, marks, dirt and other defects.

16. TAXES

16.1. Purchases made by the Owner are exempt from the payment of State Sales Tax and Federal Excise Taxes. The Contractor shall obtain from the Owner the Sales Tax Exemption Certification Number applicable to the project, and shall include said number when ordering materials for the project.

17. ROYALTIES AND PATENTS

17.1. The Contractor shall pay all royalty and license fees. He shall defend all suits and claims for infringement of any patent rights and shall indemnify and save the Owner harmless from loss on account of any such suit or claim.

18. INTERPRETATIONS

18.1. Where reference is made to standard specifications and manufacturer's instructions, it shall mean to refer to the latest edition in effect on the date of the Contractor's bid.

18.2. All headings of articles, paragraphs and subparagraphs in the specifications shall be deemed to be a part of the ensuing text and shall be taken into consideration in the interpretation or construction thereof.

19. WORKMEN'S COMPENSATION INSURANCE

19.1. Before commencing performance of the Contract, the Contractor shall provide, by insurance, for the payment of compensation and the furnishing of other benefits under Chapter 152 of the General Laws to all persons to be employed under the Contract and shall continue such insurance in full force and effect during the term of the Contract. A certificate evidencing such insurance shall be deposited with the Owner prior to execution of contact.

20. COMPREHENSIVE GENERAL LIABILITY AND PROPERTY DAMAGE INSURANCE

20.1. The Contractor shall take out and maintain during the life of the Contract, such Comprehensive General Liability Insurance as shall protect him from claims for damages for personal injury including accidental death, as well as from claims for property damage, which may arise from operations under the Contract, whether such operations by himself or by anyone directly or indirectly employed by him, and the amount of such insurance shall be as follows:

20.2. Comprehensive General Liability Insurance for personal injury in an amount not less than three hundred thousand dollars ($300,000.00) for each occurrence and in an amount not less than five hundred thousand ($500,000.00) annual aggregate.

20.3. Property Damage Insurance in an amount not less than three hundred thousand dollars ($300,000.00) for each occurrence and in an amount not less than five hundred thousand ($500,000.00)) annual aggregate.

20.4. A certificate of insurance evidencing such coverage shall be deposited with the Owner prior to execution of contract, naming the City of Woburn, MA as an additional party insured.

21. PROPERTY INSURANCE

21.1. The Contractor shall purchase and maintain in the name of the Owner, property insurance insuring the perils of fire, extended coverage, vandalism and malicious mischief on a one hundred percent (100%) value basis on the insurable portions of the work for the benefit of the Owner, the Contractor and/or his Subcontractors, as the interest of each may appear. This coverage is to remain in effect until Final Acceptance of the Work by the Owner.

21.2. A certificate of insurance evidencing such coverage shall be deposited with the Owner five (5) days of award.

22. NON-DISCRIMINATION IN EMPLOYMENT

22.1. In connection with performance of the work under the Contract, the Contractor agrees not to discriminate against any employee or applicant for employment because of race, color, religious creed, national origin, age, sex, or ancestry. The aforesaid provision shall include, but not be limited to, the following:

22.2. Employment upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; conditions or privileges of employment and selection for training, including apprenticeship.

22.3. The Contractor agrees to post hereafter in conspicuous places, available for employees and applicants for employment, notices to be provided by the Massachusetts Commission Against Discrimination setting forth the provisions of the Fair Employment Practice Law of the Commonwealth.

23. INDEMNIFICATION OF OWNER AND AGENTS

23.1. It is agreed and understood that the Contractor has made his own examinations and estimates and shall not hold the Owner, its agents or employees responsible for or bound by any schedule or estimate furnished hereunder, and shall take all responsibility for the prosecution of the work and shall bear all losses resulting to him in such prosecution of the work. He shall assume the defense of and hold the Owner, its agents and employees harmless from all suits and claims against them or any of them arising from the use of any invention, patent, or patent right, material, labor or implement in connection with the work. He shall pay all debts for labor and materials contracted for by him and for the rental of appliances and equipment hired by him. He shall conform to all requirements of law and all other public authorities, state or local, relating to the methods or materials to be used, or to the persons to be employed in doing the work. He shall indemnify and hold the Owner, the Architect, their agents and employees harmless from and against any and all claims, liability, and damages of every nature and description (including attorney's fees) related to the performance of the work which they may suffer provided that such claim, liability or damage is caused in whole or in part by any negligent act or omission of the Contractor, his agents or employees, or anyone for whose acts any of them may be liable.

24. CORRECTION OF DAMAGES AND FINAL CLEANING

24.1. The Contractor shall be fully responsible for the following performed at his own expense, and to the satisfaction of the Owner:

24.2. Repairing, replacing and/or otherwise correcting damages and flaws to items furnished by the Contractor.

24.3. Repairing, replacing and/or otherwise correcting damages and flaws to other areas caused by work performed by the Contractor.

24.4. Performing final cleaning, upon completion of the Contractor's work.

24.5. The Owner reserves the right, after giving seventy-two hour notice thereof to the Contractor, to have such defective work corrected, or to perform such cleaning, and to deduct the cost thereof from the sums otherwise due the Contractor.

25. COMMENCEMENT AND COMPLETION OF THE WORK

25.1. The work to be performed under this Contract shall be commenced upon receipt by the Owner of the signed contract; all requisite bonds, certificates of insurance and other such items as may be required by the Contract Documents.

25.2. It is anticipated that the building to receive items contained within this Contract will be available for delivery and installation on or about 01 OCTOBER 2022, provided, however, that the Contractor shall adjust its delivery and installation for a later date as necessary based on the availability of the building to receive the items contained within this Contract. The Contractor must submit a delivery and installation schedule to the Owner for the Owner's approval, providing for delivery and installation between the dates that the building is first available for receipt and the Contract Completion date. It is understood that the Contractor will need to coordinate its delivery and installation schedule with building availability and with other vendors and/or contractors. If delivery and installation occurs without written notification to the Owner, the Owner reserves the right to refuse delivery and installation of such item(s) until such time written notification is provided by the Contractor.

25.3. In no case shall installation of FURNITURE and EQUIPMENT occur later than the Contract Completion 21 OCTOBER 2022. Completion of the work shall mean on site delivered and installed as specifically described in the Contract Documents.

26. PAYMENT

26.1. When the Contractor has completed all of the work of any item, he shall submit a request for payment along with any supporting documentation required by the Owner to the Architect. Thereafter the Architect shall make an inspection of all items and work and shall forward to the Owner, a recommendation for payment based upon that inspection. The results of the inspection shall also be made known to the Contractor. Upon final completion, the Architect will recommend to the Owner 100% payment provided that the Contract has been fully performed to the satisfaction of the Architect and the Owner; for partial completion, an appropriately lesser amount may be recommended. Following receipt of the Contractor's request for payment and the Architect’s recommendation, the Owner shall make appropriate payment to the Contractor.

27. AVAILABILITY OF FUNDS

27.1. Nothing in this Contract shall be deemed to commit the Owner to pay any sum in excess of monies lawfully appropriated or available to the Owner for the purposes described in this Contract.

28. TERMINATION BY THE CONTRACTOR

28.1. If the Architect fails to certify payment for a period of thirty (30) days after request of the Contractor, through no fault of the Contractor, or if the Owner fails to make payment thereon for a period of sixty (60) days or as otherwise specified, then the Contractor may, upon thirty (30) days written notice to the Owner, terminate the Contract and recover from the Owner payment for all items delivered and installed; and for any proven loss sustained upon the materials and/or equipment, including reasonable profit and damages.

29. TERMINATION BY THE OWNER

29.1. If the Contractor defaults or neglects to carry out the delivery/installation of furnishings and/or equipment in conformance with the Contract Documents or fails to perform any provisions of the Contract, the Owner may, after seven (7) days written notice to the Contractor and without prejudice to any other remedy he may have, make good such deficiencies and may deduct the cost thereof from the payment then or thereafter due the Contractor or, at his option, may terminate the Contract and take possession of all material and equipment thereon owned by the Contractor and may finish the Contact by whatever method he may deem expedient, and if the unpaid balance of the Contract Sum exceeds the expense of finishing the Contract, such excess shall be paid to the Contractor, but if such expense exceeds such unpaid balance, the Contractor shall pay the difference to the Owner.

30. ASSIGNMENTS

30.1. Neither party to the Contract shall assign or sublet the Contract without the written consent of the other; nor shall the Contractor assign any monies due him without the written consent of the Owner.

31. AMENDMENTS

31.1. This Contract represents the entire and integrated agreement between the parties hereto and supersedes all prior negotiation, representations or agreements, either written or oral. The Contract may be amended or modified only by a written amendment signed by the Contractor and by an official of the Owner having authority to bind the Owner.

32. CONFLICT OF INTEREST

32.1. Any activity by the Contractor, his agents or employees that would constitute a violation of the conflict of interest statute, M.G.L. Chapter 268A, is hereby prohibited and shall constitute a material breach of the Contract.

END OF SECTION

SPECIAL CONDITIONS

1. LOCATION

1.1. The work is to be performed at the Woburn Fire Headquarters, 731 Main Street, Woburn, MA 01801.

2. SCHEDULE FOR PERFORMANCE OF THE WORK

2.1. The items to be provided under the contract shall be delivered and installed, as stated in paragraph 3. DEFINITION OF INSTALLATION OWNERSHIP. Please note that individual items may require more than one delivery to the same location.

2.2. At the request of the Architect and no later than 30 days before the commencement of the installation period, the Contractor shall submit his detailed schedule for delivery and installation of the work.

2.3. The Contractor shall submit all samples, furnishings, shop drawings, and mock-ups to the Architect as required by his particular items and the Contract Documents. He shall submit a copy of manufacturers' acknowledgments for each item. All submissions shall be complete within two calendar months after receipt of Contract.

3. DEFINITION OF INSTALLATION, OWNERSHIP

3.1. Installation shall have occurred when the Contractor has performed the following to the satisfaction of the Owner and as approved by the Architect. Final installation is to be reviewed by the manufacturer's representative and/or sales representative with written documentation to be submitted to the Owner stating compliance with the following:

3.1.1. Each and every item comprising the work has been furnished complete and as described in the Contract Documents.

3.1.2. The material is located, attached, connected and/or otherwise in-place as shown on the Drawings or indicated in the Specifications.

3.1.3. The material is clean and polished, and the area is free from packing as required by the General Conditions.

3.1.4. Guarantees, maintenance manuals, keys and other loose items have been delivered to the Owner.

3.1.5. Any required instruction to the Owner has been satisfactorily given.

3.2. The Contractor shall receive all materials at the site. The Contractor shall be responsible for determining whether the quantities claimed have been delivered, and whether there is no apparent damage. The Owner reserves the right to refuse delivery of any shipment if it arrives in the absence of the Contractor, or arrives on a date(s) not previously scheduled with the Owner or Architect. Such shipments shall include, but will not be limited to, third party trucking companies, and shipments direct from the manufacturer.

3.3. The Contractor shall submit to the Architect all packing slips/delivery receipts listing all items and quantities received for the project. Invoices for the delivered and installed items will not be processed without this proof of delivery.

3.4. The Contractor's installation of the materials must take place within the times approved by the Owner and the Architect and in accordance with Section 5 below.

3.5. If the Contractor obtains early delivery of materials (prior to the scheduled installation period) he shall be entirely responsible for the receiving, handling, storage and final delivery of the materials, including warehousing as may be necessary until the start of the installation period. He shall make his own arrangement with all parties concerned in this regard.

3.6. If the Owner cannot make the premises available for final installation as shown on the drawings at the time scheduled for the installation period, he shall give timely notice to the Contractor. The Contractor, at his option, may choose to make his own temporary storage arrangements or may use a space provided at the project if available for the temporary storage of his material. In such cases the Owner will endeavor to protect material; however, the Owner shall not be liable for damages incurred during this period. The Owner will make appropriate partial payment up to but not exceeding 75% of the contract value of the delivered item, during this period for material if stored on his premises and will give timely notice of the readiness of the premises for final installation. By such storage and/or partial payment the Owner shall not be deemed to have accepted nor shall the Contractor be deemed to have installed the material.

3.7. The Owner's acceptance shall take place upon final installation and completion of the work to the Owner's satisfaction in accordance with the Contract Documents. For insurance and other purposes, however, the Owner's interest shall be in direct relation to the amount of partial payment made upon the account.

3.8. If any work which has been previously accepted, specifically or by the making of payment, is found to have defects, damage, or deficiencies, of fails to conform to the Contract Documents, the Owner may revoke acceptance. Such revocation shall be made by giving prompt notice to the Contractor, and the Contractor shall promptly remedy the same at his own expense.

4. OWNER'S REMEDY FOR DELAY

4.1. It is understood and agreed that time is of the essence of this Contract. If the Contractor fails to achieve final completion of any portion of the work by the applicable Contract Completion Date, the Owner shall, without prejudice to any other remedy the Owner may have, require that the Contractor supply similar items deemed suitable by the Owner on a temporary basis for the intended use. These items must be placed in accordance with the Contract Documents and removed by the Contractor at the time of installation of the actual items purchased. Such temporary furnishings or equipment must be installed in conformance with the scheduled completion dates set forth in the contract at no cost to the owner.

4.2. As an alternative remedy to paragraph 4.1 the Owner may assess liquidated damages in the amount of $250.00 dollars per day for each day after the Contractor has failed to complete its work.

4.3. The whole or any part of said remedy for delay may be waived by the Owner in writing at the Owner's sole discretion if the Owner determines the operation of the school will not be affected by the absence of such furnishings.

5. HOURS OF WORK

5.1. The Contractor shall furnish sufficient forces to insure the prosecution of work in accordance with the schedule. If the installation of the material is not complete by the appropriate Contract completion date, then the Contractor shall, at the Owner's request, carry out all remaining installation work outside school hours, at no extra cost to the Owner, so as to avoid disturbing normal school activities.

5.2. Subject to 5.1 above, work shall be performed during normal working hours, starting no sooner than 7:00AM, weekdays or 8:00AM on Saturday, except work may be performed on night shifts, overtime, Sundays and holidays when permission to do so has been obtained from the Owner.

5.3. The Contractor will not be entitled to additional compensation for extra shifts or overtime work required to perform the work unless the Owner specifically agrees to assume such payment obligation in advance of authorizing such additional compensation.

6. FIRE RESISTANCE

6.1. Applicable regulations: All items furnished shall comply with the current requirements of 527 CMR 21.00 "Flammable Decorations" and 527 CMR 29.00 "Upholstered Furniture", which is part of the Commonwealth of Massachusetts Department of Public Safety Board of Fire Prevention Regulations 527 CMR 1.00- 50.00 dated December 31, 2014, and as amended.

7. MAINTENANCE INSTRUCTIONS

7.1. The Contractor must supply the Owner with satisfactory instructions on the proper maintenance of all items covered in this Contract.

8. MANUFACTURERS' WARRANTIES

8.1. In addition to the guarantee requirement of the General Conditions, certain equipment is warranted to the original purchaser for longer periods to be free from defects in material and workmanship. In order for the Owner to benefit from such warranties, the Contractor shall forward copies of the manufacturer's standard warranty forms to the Owner as a condition of the Owner's final acceptance of such equipment.

9. SHOP DRAWINGS

9.1. Where required in the specifications, shop drawings shall be submitted. All drawings shall be at minimum 1/4" scale giving accurate as-built conditions where relevant, accurate rough-in dimensions and exact indication of connections to all services. The Contractor must supply detailed specification information as requested, must submit three sets of prints for each shop drawing to the Architect, and shall begin no affected portions of the work before approval of shop drawings.

10. PROJECT COMMUNICATION

10.1. Communication between the Contractor shall be through the Architect, as the representative of the Owner during the Contract period. The Contractor shall make no direct communication with the Owner without first notifying the Architect. If, in any circumstance, such direct communication occurs, it is to be made in writing with a copy sent simultaneously to the Architect.

END OF SECTION

BID PROPOSAL INSTRUCTIONS

1. INSTRUCTIONS TO BIDDERS

1.1. The following Bid Proposal Form is to be used to provide unit and total cost based on the coded items in the Technical Specifications.

1.2. If an item is bid as specified, exactly matching all criteria in the Technical Specification provide the unit price and total price based on the total quantity, ONLY.

1.3. If an alternate or modification to the Technical Specification is proposed, include on the bid form the Alternate Manufacturer and Model Number for that item. All alternates MUST be accompanied by catalog cuts, specifications, drawings or other supportive literature and clearly labeled with the Item Code to match the Item Code from the Technical Specifications.

1.4. NOTE: If there are any discrepancy between the Unit Price and the Total Price based on the given Quantity, the Unit Price will prevail.

1.5. In addition to the PDF documents provided, a Microsoft Excel spreadsheet of the Bid Proposal Form is included. Bidders are requested to fill this out, as noted above, and submit it along with the required “printed” documents, as an electronic file on either a thumb drive. As an alternate to this, Bidders may email, directly to DiNisco Design, Inc. the completed electronic copy of the Microsoft Excel spreadsheet to m.hestand@dinisco.com. THIS CAN NOT BE SENT UNTIL AFTER THE SCHEDULED BID OPENING and received no later than 5:00 PM, Friday, April 15, 2022.

2. BIDDER’S PROJECT MANGER

2.1. Provide the name and contact information for the individual who would be the Project Manager. This individual will be the prime contact for all aspects of the project; to include, but not limited to deliveries, on site supervision of installers, punch list resolution, etc.

Name: _____

Phone Number: _____ Cell Number: _____

Email: _____

3. BIDDER'S INSTALLATION

3.1. The means and methods of installation is critical to the successful and timely completion of this project. The above-named Project Manager will be responsible for the on-site management of all individuals of their installers.

3.2. Depending on the conditions of the site and the completion of the work of the General Contractor, installers may be required to have and wear basic safety equipment, hard hats, safety vests, hard sole shoes, etc.

3.3. On the line below, provide the name of the anticipated installation company, if not being done directly by the Bidders own employees.

Company Name: _____

NOTE to BIDDERS - reference SPECIFICATION pages for required options and finishes for each item listed below. Bidders that indicated an item bid "AS SPEC'D" shall meet all the requirements as documented in the SPECIFICATIONS.

Insert Unit Cost below and Total Cost will

Quantity	Item Number	Item	Description	Unit Cost	Total Cost
3	01.CH.SLLAPC	Side Chair, Arms, Casters	KI Strive – SSLAPC		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
20	01.CH.SLLAUB	Side Chair, Arms, Upholstered Seat & Back	KI Strive – SLLAUB		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
21	01.CH.SLLAUBC	Side Chair w/ Arms & Casters	KI Strive – SLLAUBC		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
12	01.CH.SLNAP	Armless Side Chair	KI Strive – SLNAP		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
64	01.CH.SWNAU	Stacking Chair, Sled Base, Armless	KI Strive – SWNAU		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
4	01.CH.SWNAUD	Chair Cart	KI Transport Dolly		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	01.CT.0002	Task Chair, Full Back, Height & Width Adjustable Arms	Steelcase Crew TS-30821		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
4	02.CD.0001	Counter Height Stools	National Office Furniture – Grin N49GMD1		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
12	02.CD.0002	Dining Chairs	National Office Furniture – Grin N49GUW		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
18	02.CH.0001	Task Chair - High Back	SitOnIt Novo		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
3	02.CH.0001C	Task Chair - High Back, Carpet Caster	SitOnIt Novo		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
6	02.CL.0002	Leather Recliner	Dream Seat HT Recliner		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	02.CL.0003	1-Seat Lounge Chair	National Office Furniture Collette N84L1A		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
4	02.CT.3060	Conference Table w/ Casters	SurfaceWorks Elements TTE.R.3060.EB		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	02.CT.3660	Conference Table w/ Casters	SurfaceWorks Element TTE.R.3660.EB		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	02.CT.3672	Conference Table w/ Casters	SurfaceWorks Element TTE.R.3672.EB		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	02.SL.0001	Large Sofa, 3-Seat Lounge	National Office Furniture Collette N84L3A		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	02.SL.0002	Large Sofa, 2-Seat Lounge	National Office Furniture Collette N84L2A		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
3	02.ST.0001	Side Table	National Office Furniture Footings X-Base CBV2119XBP		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			

NOTE to BIDDERS - reference SPECIFICATION pages for required options and finishes for each item listed below. Bidders that indicated an item bid "AS SPEC'D" shall meet all the requirements as documented in the SPECIFICATIONS.

Insert Unit Cost below and Total Cost will

Quantity	Item Number	Item	Description	Unit Cost	Total Cost
1	02.ST.0002	Side Table, Soft Square	National Office Furniture Footings X-Base CBV2119XBP (Soft Square)		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
26	02.TT.0001	Training Tables	MityLite Linenless Fixed Width		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
4	02.TT.0001A	Table Cart	MityLite RT Reveal Cart		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	03.TD.0001	Dining Table	Surfaceworks Rapport T-Leg RPC.R.48144		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
16	03.VF.0005	5-Drawer Vertical File	Hon 210 Series H215C.P.Q		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
5	04.BK.3628	2-Shelf Bookcases	Great Openings Trace GBS 3628		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
4	04.BK.3652	4-Shelf Bookcase	Great Openings Trace GBS 3652		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
8	04.BK.3666	5-Shelf Bookcase	Great Openings Trace GBS 3666		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
5	04.BK.4266	5-Shelf Bookcase	Great Openings Trace GBS 4266		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	05.FP.03FF	2-Drawer Pedestal File	Great Openings Trace EL 5109		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
18	05.LF.0236	2-Drawer Lateral File	Great Openings Trace C401		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
4	05.LF.0436	4-Drawer Lateral File	Great Openings Trace D103		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
19	05.MP.03BF	3-Drawer Mobile Pedestal	Great Openings Trace EL 1819		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
8	06.BB.0001	XL Twin Bunk	Norix Protégé NextGen Steel Single Bed		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
8	06.BB.0002	Nightstand	Norix Protégé Nightstand PROT700		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	06.MB.0001	Twin XL Murphy Bed	Murphy Wall-Beds Build-a-Bed		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	06.MB.0001ANF	Twin XL Mattress	Clover Mattress		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
8	06.MB.0001A	Twin XL Mattress	Clover Mattress w/ Twin XL 5.5" Standard Foundation		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
3	07.AB.0001	50-Gallon Waste Bin	Rubbermaid 9W27 Brute 50-Gallon		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
3	07.AB.0002	50-Gallon Recycling Bin	Rubbermaid Brute 50-Gallon Recycling		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			

NOTE to BIDDERS - reference SPECIFICATION pages for required options and finishes for each item listed below. Bidders that indicated an item bid "AS SPEC'D" shall meet all the requirements as documented in the SPECIFICATIONS.

Insert Unit Cost below and Total Cost will

Quantity	Item Number	Item	Description	Unit Cost	Total Cost
5	07.AB.0003	Floor Pad Cart	Global Industrial T97952504		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
54	07.AB.0004	Floor Protection Pads	Sundance Mat 4 x 6 Ft x 3/4 inch Straight Edge Standard		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
25	07.ALL.0001	28-Quart Trash Can	Rubbermaid 2956 Wastebasket		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
22	07.ALL.0007	7-Gallon Recycling Bin	Rubbermaid 2956-73 Deskside Recycling Container, Medium w/ Universal Symbol		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
3	07.ALL.0010	10-Gallon Recycling Bin	Rubbermaid H-1859BLU		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	07.ALL.0010	10-Gallon Recycling Container	Rubbermaid 2957		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	07.FS.0001	Walk Behind Floor Scrubber	Tennant T2		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
18	07.MS.1992	Waste Receptacle	Rubbermaid Slim Jim 1901992		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	07.OF.0001	Blueprint Rack	Interion by Global Industrial 298701		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	07.OF.0001A	Blueprint Rack Clamps (Set of 6)	Brookside Design PC642		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	07.OS.0001	Coffee Maker	Bunn Heat N' Brew Coffee Maker 10 cup		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	07.TR.0001	Reclining Patient Chair	Winco Extra Large Three-Position Recliner		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	07.TR.0002	Treatment Table	Clinton Industries 3020-30		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	07.TR.0003	AED	Physio Control Lifepak 1000		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	07.TR.0004	Portable O2	Tri-Med M9 Cylinder w/ Bag		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	07.TR.0005	Sharps Container	COVIDIEN Auto Drop Sharps Container		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	08.DS.0001	Outdoor Dining Set	Polywood Lakeside 7-piece Farmhouse Dining Set		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	09.CB.0001A	Cylinder Wall Bracket	USA Safety GB110FS		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	09.CB.0001B	Cylinder Wall Bracket	USA Safety 4-Cylinder Wall Bracket #GB401FS		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	09.CC.0001	Cylinder Cart	Global Industrial WGB1461324		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			

NOTE to BIDDERS - reference SPECIFICATION pages for required options and finishes for each item listed below. Bidders that indicated an item bid "AS SPEC'D" shall meet all the requirements as documented in the SPECIFICATIONS.

Insert Unit Cost below and Total Cost will

Quantity	Item Number	Item	Description	Unit Cost	Total Cost
1	09.CC.0002	Mobile O2 Cylinder Cart	USA Safety GCMDE24SC		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	09.NC.LNC5	Narcotics Cabinet	Lakeside SKU #LNC-5		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	09.SC.3619	Antimicrobial Cabinet	Hallowell Antimicrobial Storage Cabinet 800 Series		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	09.TC.0001	13-Drawer Tool Storage Cabinet & Chest	Global Industrial T97535487		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	09.UC.3352	Mobile Stainless Steel Utility Cart	ULine H-3352		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	09.WB.0001	Panel Leg Workbench	Global Industrial WG250230		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	09.WB.0001B	Panel Leg Workbench Power Riser	Global Industrial WG254744		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	09.WB.0001C	Panel Leg Workbench Steel Drawer	Global Industrial WG606964		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	09.WB.0002	Mobile Adjustable Height Workbench	Global Industrial WG183149A		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	09.WB.0003	Workbench - 96" x 36"	ULine H-1222-STEEL		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	10.BF.CFS5	3-Bottle Fill Station	Bauer CFS5.5-3S/SF/TM Containment Fill Station		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	10.CC.0001	SCBA Compressor	Bauer Verticus VAC13H-E3		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	10.CC.0002	SCBA Compressor CO Monitor	Bauer GT/CO/III		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	10.CM.RFID	Fill Station RFID	Bauer RFID-Pro Cylinder Management System		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	10.CS.0001	SCBA Cascade Cylinder Storage System	Bauer ASME 6K-4 + RCK-0037 (2 pack)		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	10.RR.0001	Remote Reel	Bauer HR/REL-9/N-C		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	10.RS.0001	Remote Start	Bauer ASY-1069		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.AH.0001	Antifreeze Handler	Gray AH-15		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.CR.0001	Cable Reel Rack	Stromberg CR4836120		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
3	M01.CS.0032	SCBA Cylinder Storage	Geargrid Mini Mobile 02 Cylinder System		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	M01.DD.0001	2-Drum Drip Deck	PIG Poly Drip Deck PAK565		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			

NOTE to BIDDERS - reference SPECIFICATION pages for required options and finishes for each item listed below. Bidders that indicated an item bid "AS SPEC'D" shall meet all the requirements as documented in the SPECIFICATIONS.

Insert Unit Cost below and Total Cost will

Quantity	Item Number	Item	Description	Unit Cost	Total Cost
2	M01.DJ.0001	Portable Drum Jack	Vestil DRUM-55-36		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.FA.0001	Desk	Alera Steel Double Pedestal Desk - T9AB1144836		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.OH.0001	Oil Handler	Gray OH-15		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.PR.0001	Pipe Rack	Global Industrial WG245648		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.UC.0001	Undercarriage Cleaning System	Mosmatic Hurricane High Lift Model # TUW-520		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.WR.0001S	Mesh Work Stool	ULine H-5498		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	M01.WR.0001	Wheel Ramps	Gray PTRW-20		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
3	M01.WR.0002	Flammable Cabinet	Global Industrial Part # 298541		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.WR.0003	Bench Grinder	DeWalt DW758		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.WR.0004	Drill Press	Delta 18-900L		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.WR.0005	Oil Filter Crusher	Gray QP-50		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.WR.0006	20-Gallon Parts Washer	Eastwood 14293		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.WR.0007	25-Ton Shop Press	Gray SP-25		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.WR.0008	Tire Changer	Hunter TC39		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
2	M01.WR.0009	13-Drawer Tool Storage Cabinet	Global Industrial WG535653		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	M01.WR.0010	Wheel Balancer	Hunter SmartWeight Pro		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	SB.OT.0001	Waste Oil Tank	Snyder Industries Model No. 5700102N5703		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			
1	SB.OT.0002	Oil & Antifreeze Waste Storage Disposal	Snyder Industries Model No. 5700102N5703		$0.00
	__As Spec'd __Alternate	*Alternate Mfg/Model:*			

Total Bid **$0.00**

CODE 01.CH.SLLAPC Side Chair, Arms, Casters

QTY 3 MFG / MODEL KI Strive – SSLAPC

DIMENSIONS 25" W x 22-1/4" D x 32-7/8" H; 18" SH

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
101 LOBBY
102 FIRST AID & TRIAGE

SPECIFICATION

GENERAL: 4-leg stacking chair with padded polypropylene seat & padded flexing back.
BACKREST: Shall be constructed of injection-molded polypropylene with integral steel cantilever springs. The combination of the slotted polypropylene back and the spring steel shall provide a supportive flexing back. Springs shall be nominal 4.5mm diameter chrome silicon valve spring wire.
SEAT & SHROUD: Shall be injection-molded polypropylene.
UPHOLSTERED SEAT: Molded urethane foam shall be attached to an injection-molded polypropylene seat board, then upholstered using a draw-string process. The assembled seat pad shall be attached to the seat by means of hidden fasteners.
UPHOLSTERED BACK: 1/2" thick urethane foam shall be attached to an injection-molded polypropylene back board, then upholstered using a draw-string process. The assembled back pad shall be attached to the back by means of fasteners which shall be exposed and shall be color matched to the polypropylene.
FRAME: Legs shall be 7/8" O.D. x 13-gauge tubular steel. Cross members shall be 1" O.D. x 14-gauge tubular steel and 7/16" diameter solid steel. All joints shall be welded. Standard 4-leg rear legs angle 14 from vertical. Wallsaver rear legs angle 23° from vertical.
FINISH: Baked-on electrostatically applied 30 gloss epoxy powder-coating
ARMS: Provide cantilever arms. The supporting structure shall be a continuation of the rear leg finished to match the frame color. The armcaps shall be injection-molded glass filled polypropylene matching the frame finish (when frame finish is Chrome, hammertones, or Starlight Silver metallic, armcaps shall match the seat and back color; when back is Diamond translucent, armcaps shall be Light Tone; when back is Pewter translucent, armcaps shall be Flannel; when back is Bronze translucent, armcaps shall be Chocolate). The armcaps shall be attached to the steel structure by means of screws.
CASTERS: Casters shall be double-wheel (60mm) high-impact thermoplastic and shall be available in black only.

CODE 01.CH.SLLAUB Side Chair, Arms, Upholstered Seat & Back

QTY 20 MFG / MODEL KI Strive – SLLAUB

DIMENSIONS 25" W x 22-1/4" D x 32-1/2" H; 18" SH

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
113 PAYROLL / ARSON
115 PERMITS / OIL BURNER
116 EMS / TRAINING
118 DEPUTY CHIEF
121 ADMIN ASSISTANT
122 FIRE PREVENTION

SPECIFICATION

GENERAL: Wallsaver rear legs touch base of wall preventing chair back from contacting wall surface. 4-leg stacking chair with padded polypropylene seat, & padded flexing back.
BACKREST: Shall be constructed of injection-molded polypropylene with integral steel cantilever springs. The combination of the slotted polypropylene back and the spring steel shall provide a supportive flexing back. Springs shall be nominal 4.5mm diameter chrome silicon valve spring wire.
SEAT & SHROUD: Shall be injection-molded polypropylene.
UPHOLSTERED SEAT: Molded urethane foam shall be attached to an injection-molded polypropylene seat board, then upholstered using a draw-string process. The assembled seat pad shall be attached to the seat by means of hidden fasteners.
UPHOLSTERED BACK: 1/2" thick urethane foam shall be attached to an injection-molded polypropylene back board, then upholstered using a draw-string process. The assembled back pad shall be attached to the back by means of fasteners which shall be exposed and shall be color matched to the polypropylene.
FRAME: Legs shall be 7/8" O.D. x 13-gauge tubular steel. Cross members shall be 1" O.D. x 14-gauge tubular steel and 7/16" diameter solid steel. All joints shall be welded. Standard 4-leg rear legs angle 14 from vertical. Wallsaver rear legs angle 23 from vertical.
FINISH: Baked-on electrostatically applied 30 gloss epoxy powder-coating
ARMS: Provide loop arms. The supporting structure shall be a continuation of the rear leg finished to match the frame color. The armcaps shall be injection-molded glass filled polypropylene matching the frame finish (when frame finish is Chrome, hammertones, or Starlight Silver metallic, armcaps shall match the seat and back color; when back is Diamond translucent, armcaps shall be Light Tone; when back is Pewter translucent, armcaps shall be Flannel; when back is Bronze translucent, armcaps shall be Chocolate). The armcaps shall be attached to the steel structure by means of screws.
GLIDES: Upper and lower ends of leg tubes shall be capped with polypropylene end caps matching leg color.

CODE 01.CH.SLLAUBC Side Chair, Arms, Upholstered Seat & Back, Casters

QTY 21

MFG / MODEL KI Strive

DIMENSIONS 25" W x 22-1/4" D x 32-7/8" H; 18" SH

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
119 CHIEF
123 CONFERENCE

SPECIFICATION

GENERAL: Wallsaver rear legs touch base of wall preventing chair back from contacting wall surface. 4-leg stacking chair with padded polypropylene seat, & padded flexing back.
BACKREST: Shall be constructed of injection-molded polypropylene with integral steel cantilever springs. The combination of the slotted polypropylene back and the spring steel shall provide a supportive flexing back. Springs shall be nominal 4.5mm diameter chrome silicon valve spring wire.
SEAT & SHROUD: Shall be injection-molded polypropylene.
UPHOLSTERED SEAT: Molded urethane foam shall be attached to an injection-molded polypropylene seat board, then upholstered using a draw-string process. The assembled seat pad shall be attached to the seat by means of hidden fasteners.
UPHOLSTERED BACK: 1/2" thick urethane foam shall be attached to an injection-molded polypropylene back board, then upholstered using a draw-string process. The assembled back pad shall be attached to the back by means of fasteners which shall be exposed and shall be color matched to the polypropylene.
FRAME: Legs shall be 7/8" O.D. x 13-gauge tubular steel. Cross members shall be 1" O.D. x 14-gauge tubular steel and 7/16" diameter solid steel. All joints shall be welded. Standard 4-leg rear legs angle 14 from vertical. Wallsaver rear legs angle 23 from vertical.
FINISH: Baked-on electrostatically applied 30 gloss epoxy powder-coating
ARMS: Provide loop arms. The supporting structure shall be a continuation of the rear leg finished to match the frame color. The armcaps shall be injection-molded glass filled polypropylene matching the frame finish (when frame finish is Chrome, hammertones, or Starlight Silver metallic, armcaps shall match the seat and back color; when back is Diamond translucent, armcaps shall be Light Tone; when back is Pewter translucent, armcaps shall be Flannel; when back is Bronze translucent, armcaps shall be Chocolate). The armcaps shall be attached to the steel structure by means of screws.
CASTERS: Casters shall be double-wheel (60mm) high-impact thermoplastic. High-impact plastic frame. Hard floor casters are black only.

CODE 01.CH.SLNAP Armless Side Chair

QTY 12

MFG / MODEL KI Strive – SLNAP

DIMENSIONS 20-5/8" W x 22-1/4" D x 32-1/2" H; 18" SH

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
132 READY ROOM

SPECIFICATION

GENERAL: 4-leg stacking chair with polypropylene seat & flexing back.
BACKREST: Shall be constructed of injection-molded polypropylene with integral steel cantilever springs. The combination of the slotted polypropylene back and the spring steel shall provide a supportive flexing back. Springs shall be nominal 4.5mm diameter chrome silicon valve spring wire.
SEAT: Shall be injection-molded polypropylene.
FRAME: Legs shall be 7/8" O.D. x 13-gauge tubular steel. Cross members shall be 1" O.D. x 14-gauge tubular steel and 7/16" diameter solid steel. All joints shall be welded. Standard 4-leg rear legs angle 14 from vertical. Wallsaver rear legs angle 23 from vertical.
FINISH: Baked-on electrostatically applied 30 gloss epoxy powder-coating
GLIDES: Shall be non-marring and appropriate for hard floors.

CODE 01.CH.SWNAU Stacking Chair, Sled Base, Armless

QTY 64 MFG / MODEL KI Strive – SWNAU

DIMENSIONS 19-1/2" W x 22-1/4" D x 32-1/2" H; 18" SH

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
103 MEET / TRAIN

SPECIFICATION

GENERAL: 4-leg stacking chair with polypropylene seat & flexing back.
BACKREST: Shall be constructed of injection-molded polypropylene with integral steel cantilever springs. The combination of the slotted polypropylene back and the spring steel shall provide a supportive flexing back. Springs shall be nominal 4.5mm diameter chrome silicon valve spring wire.
SEAT & SHROUD: Shall be injection-molded polypropylene.
FRAME: Legs shall be 7/8" O.D. x 13-gauge tubular steel. Cross members shall be 1" O.D. x 14-gauge tubular steel and 7/16" diameter solid steel. All joints shall be welded. Provide sled base frame configuration.
FINISH: Baked-on electrostatically applied 30 gloss epoxy powder-coating
GLIDES: Upper and lower ends of leg tubes shall be capped with polypropylene end caps matching leg color.

CODE 01.CH.SWNAUD Chair Cart

QTY 4 MFG / MODEL KI Transport Dolly

DIMENSIONS 22-3/8" W x 25-5/8" D

FINISHES Black

DISTRIBUTION
103B TABLES / CHAIRS

SPECIFICATION

Accommodates up to 30 poly chairs
(4) 5" casters: two fixed, two swivel
Black powder-coated finish

CODE 01.CT.0002 Task Chair, Full Back, Height & Width Adjustable Arms

QTY 2 MFG / MODEL Steelcase Crew TS-30821

DIMENSIONS Overall: 26" D x 26-1/2" W x 39-5/8"-44-5/8" H
SH: 16"-21"; Functional Seat Depth: 18"

FINISHES Architect shall select from manufacturers complete range of standard finishes.
Upholstery: TBD - Grade 2

DISTRIBUTION
131 WATCH ROOM

SPECIFICATION

- Synchro-tilt mechanism
- Pneumatic seat height
- Upright back lock
- Tilt tension
- Back height adjustment
- Upholstered seat and inner back: fabric price group 2
- Outer back: black plastic
- Five-arm base: black plastic
- Width-adjustable arms, if arms selected: 0835 Black
- Adjustable foot ring on stools only: 9201 Polished Chrome
- Hard dual-wheel casters: black
- Shipped ready to assemble with no tools required

CODE 02.CD.0001 Counter Height Stools

QTY 4 MFG / MODEL National Office Furniture – Grin N49GMD1

DIMENSIONS 18-1/2" W x 18-3/4" D x 36-1/2" H
Seat Height: 30-1/2"; Seat Depth: 15-3/4"; Seat Width 18-1/4

FINISHES Architect shall select from manufacturers complete range of standard finishes.
Upholstery: TBD - Grade 3; Footrest: Polished

DISTRIBUTION
207 KITCHEN / DINING

SPECIFICATION

SEAT AND BACK CONSTRUCTION
• ½" molded plywood, cross banded for strength, forms seat and back
• ¾" of high-grade polyurethane foam covers seat and back
FRAME
4-Leg Wood Frame
• Maple wood species
• 1/2" tubular steel footrest
• Non-marring nylon glides
UPHOLSTERY
• No stitch option

CODE 02.CD.0002 Dining Chairs

QTY 12 MFG / MODEL National Office Furniture – Grin N49GUW

DIMENSIONS 19-3/4" W x 22-1/2" D x 32-3/4" H;
Seat Height: 18-1/4"; Seat Depth: 17" ; Seat Width: 18-1/4"

FINISHES Architect shall select from manufacturers complete range of standard finishes.
Upholstery: TBD - Grade 3

DISTRIBUTION
207 KITCHEN / DINING

SPECIFICATION

SEAT AND BACK CONSTRUCTION
• ½" molded plywood, cross banded for strength, forms seat and back
• ¾" of high-grade polyurethane foam covers seat and back
FRAME
4-Leg Wood Frame
• Maple wood species
• Non-marring nylon glides
UPHOLSTERY
• No stitch option

CODE 02.CH.0001 Task Chair - High Back

QTY 18 MFG / MODEL SitOnIt Novo

DIMENSIONS 27" W x 26" D x 39" H

FINISHES Frame: Mesh: Upholstery:

DISTRIBUTION
113 PAYROLL / ARSON
115 PERMITS / OIL BURNER
116 EMS / TRAINING
118 DEPUTY CHIEF
119 CHIEF
122 FIRE PREVENTION
123 CONFERENCE
204 STUDY
M101 OFFICE
M103 FIRE ALARM & TRAFFIC

SPECIFICATION

GENERAL: The chair shall have standard synchro tilt mechanism, upholstered seat, mesh back and 5-star base. Chair shall have a 300 lb. weight capacity.
SEAT: Shall be 10-ply 5/8" molded plywood. Molded high resiliency foam shall be 2" thick with a Density/IFD of 3.0/35. Seat shall have depth adjustment and waterfall front.
BACK: Shall consist of a 1" diameter 14-gauge steel tube yoke, glass filled nylon back, and BK2 high back mesh. It shall feature adjustable lumbar support.
ARMS: Arms shall be multi-adjustable (AR6). The arm shall be textured molded polypropylene.
BASE: Shall be 26" diameter, 5-star type made of glass filled molded nylon.
CASTERS: Shall be "hard floor" type (CS6).
WARRANTY: Lifetime: Cylinder, control, base, casters, glides, frames; 12 years for 24/7 use; 5 Years: Fabric, Foam, Plastic, Mesh

CODE 02.CH.0001C Task Chair - High Back, Carpet Caster

QTY 3 MFG / MODEL SitOnIt Novo

DIMENSIONS 27" W x 26" D x 39" H

FINISHES Frame: Mesh: Upholstery:

DISTRIBUTION
121 ADMIN ASSISTANT
213B DUTY OFFICER
202 SHIFT SUPERVISOR

SPECIFICATION

GENERAL: The chair shall have standard synchro tilt mechanism, upholstered seat, mesh back and 5-star base. Chair shall have a 300 lb. weight capacity.
SEAT: Shall be 10-ply 5/8" molded plywood. Molded high resiliency foam shall be 2" thick with a Density/IFD of 3.0/35. Seat shall have depth adjustment and waterfall front.
BACK: Shall consist of a 1" diameter 14-gauge steel tube yoke, glass filled nylon back, and BK2 high back mesh. It shall feature adjustable lumbar support.
ARMS: Arms shall be multi-adjustable (AR6). The arm shall be textured molded polypropylene.
BASE: Shall be 26" diameter, 5-star type made of glass filled molded nylon.
CASTERS: Shall be "soft floor" type (CS5).
WARRANTY: Lifetime: Cylinder, control, base, casters, glides, frames; 12 years for 24/7 use; 5 Years: Fabric, Foam, Plastic, Mesh

CODE 02.CL.0002 Leather Recliner

QTY 6 MFG / MODEL Dream Seat HT Recliner

DIMENSIONS 43" H x 37" W x 40" D

FINISHES Brown

DISTRIBUTION
206 LIVING ROOM

SPECIFICATION

Seat Height: 20"
Seat Depth: 22"
Fully Reclined: 68"
Weight: 105 lbs.
- 2 Stainless Steel Cup Holders
- Synthetic leather in all touch areas
- Chaise Support: Provides continuous head–to–toe support when reclined
- Limited Lifetime Warranty
- Available in a black or brown
- Removable back for easier delivery and moving from room to room
- Available with a Power Recline

CODE 02.CL.0003 1-Seat Lounge Chair

QTY 2

MFG / National Office Furniture
MODEL Collette N84L1A

DIMENSIONS 40" W x 35-1/2" D x 34-1/2" H; SH: 18-1/2"; Seat Depth: 22" ; Seat Width: 30"

FINISHES Architect shall select from manufacturers complete range of standard finishes.
Upholstery: TBD - Grade 3

DISTRIBUTION
207 KITCHEN / DINING

SPECIFICATION

FRAME CONSTRUCTION
• Interior frame is constructed of oriented strand board with tenon joints that are glued and stapled for maximum joint stability
• Frames and table platforms are wrapped in high grade polyurethane foam, custom shaped, fabricated, and slip-covered
SEAT CONSTRUCTION
• Seat cushions are attached to frame and feature an 8-1⁄2" cushion constructed of an inner steel springcoil pack enveloped by high grade polyurethane foam
BACK CONSTRUCTION
• Back pillows are attached to back frame and feature a recycled polyester filled insert
• Back and seat cushions are attached but replaceable
ARM CONSTRUCTION
• Arms are wrapped in high grade polyurethane foam, custom shaped, fabricated and slip-covered
• Arms are connected to frame using 4 bolts per arm
UPHOLSTERY DETAILS
• Top stitch is a French seam and is offered in matching or contrasting thread colors, except on tables
• Comfort wrinkles on the seat and back cushions are an inherent part of the design
• Contrasting fabric available on all models, except tables
LEGS
• Wood square legs offered in all National seating finishes
• When specifying Brighton, Sonoma, and Natural finish, variation in color is acceptable due to the nature of wood characteristics
• Features 1" adjustable nylon leveling glides

CODE 02.CT.3060 Conference Table w/ Casters

QTY 4

MFG / SurfaceWorks Elements
MODEL TTE.R.3060.EB

DIMENSIONS 60" W x 30" D x 30" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
123 CONFERENCE

SPECIFICATION

TOP: Top shall be 1-1/8" thick superior M3 industrial grade 47# density particle board, finished with high pressure laminate on top side and a backer of matched grade of laminate on bottom for the greatest resistance to deflection.
BASE: Shall be welded/bolted base for maximum strength and durability with positive-locking flip mechanism. Base shall have 2" diameter, 14 gauge column and feet. The legs shall be attached to top by a 13/16" thick x 5" x 8" steel mounting plate.
CASTERS: 2" dual wheel locking.
GANGING MECHANISM: Tables shall have "Pop & Lock" table connectors constructed of high-density plastic. Connector shall consist of tow identical pieces and shall be engaged by rotating the locks' arms and popping them into place.

CODE 02.CT.3660 Conference Table w/ Casters

QTY 1

MFG / SurfaceWorks Element
MODEL TTE.R.3660.EB

DIMENSIONS 60" W x 36" D x 30" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
119 CHIEF

SPECIFICATION

TOP: Top shall be 1-1/8" thick superior M3 industrial grade 47# density particle board, finished with high pressure laminate on top side and a backer of matched grade of laminate on bottom for the greatest resistance to deflection.
BASE: Shall be welded/bolted base for maximum strength and
durability with positive-locking flip mechanism. Base shall have 2" diameter, 14 gauge column and feet. The legs shall be attached to top by a 13/16" thick x 5" x 8" steel mounting plate.
CASTERS: 2" dual wheel locking.
GANGING MECHANISM: Tables shall have "Pop & Lock" table connectors constructed of high-density plastic. Connector shall consist of tow identical pieces and shall be engaged by rotating the locks' arms and popping them into place.

CODE 02.CT.3672 Conference Table w/ Casters

QTY 2

MFG / SurfaceWorks Element
MODEL TTE.R.3672.EB

DIMENSIONS 72" W x 36" D x 30" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
132 READY ROOM

SPECIFICATION

TOP: Top shall be 1-1/8" thick superior M3 industrial grade 47# density particle board, finished with high pressure laminate on top side and a balanced backer on bottom for the greatest resistance to deflection.
BASE: Shall be fully welded with 2" diameter, 14 gauge column and feet. The legs shall be attached to top by a 13/16" thick x 5" x 8" steel mounting plate.
GLIDES: The legs shall feature adjustable levelers of 1-3/8" diameter and 5/16" - 18 stud with nylon foot.
GANGING MECHANISM: Provide Ganging Mechanisms so tables can attach to each other to create a large surface.

CODE 02.SL.0001 Large Sofa, 3-Seat Lounge

QTY 1

MFG / National Office Furniture
MODEL Collette N84L3A

DIMENSIONS 100" W x 35-1/2" D x 34-1/2" H; SH: 18-1/2"; Seat Depth: 22" ; Seat Width: 90"

FINISHES Architect shall select from manufacturers complete range of standard finishes.
Upholstery: TBD - Grade 3

DISTRIBUTION
207 KITCHEN / DINING

SPECIFICATION

FRAME CONSTRUCTION
• Interior frame is constructed of oriented strand board with tenon joints that are glued and stapled for maximum joint stability
• Frames and table platforms are wrapped in high grade polyurethane foam, custom shaped, fabricated, and slip-covered
SEAT CONSTRUCTION
• Seat cushions are attached to frame and feature an 8-1⁄2" cushion constructed of an inner steel springcoil pack enveloped by high grade polyurethane foam
BACK CONSTRUCTION
• Back pillows are attached to back frame and feature a recycled polyester filled insert
• Back and seat cushions are attached but replaceable
ARM CONSTRUCTION
• Arms are wrapped in high grade polyurethane foam, custom shaped, fabricated and slip-covered
• Arms are connected to frame using 4 bolts per arm
UPHOLSTERY DETAILS
• Top stitch is a French seam and is offered in matching or contrasting thread colors, except on tables
• Comfort wrinkles on the seat and back cushions are an inherent part of the design
• Contrasting fabric available on all models, except tables
LEGS
• Wood square legs offered in all National seating finishes
• When specifying Brighton, Sonoma, and Natural finish, variation in color is acceptable due to the nature of wood characteristics
• Features 1" adjustable nylon leveling glides

CODE 02.SL.0002 Large Sofa, 2-Seat Lounge

QTY 1

MFG / National Office Furniture
MODEL Collette N84L2A

DIMENSIONS 70" W x 35-1/2" D x 34-1/2" H; SH: 18-1/2"; Seat Depth: 22" ; Seat Width: 60"

FINISHES Architect shall select from manufacturers complete range of standard finishes.
Upholstery: TBD - Grade 3

DISTRIBUTION
131 WATCH ROOM

SPECIFICATION

FRAME CONSTRUCTION
• Interior frame is constructed of oriented strand board with tenon joints that are glued and stapled for maximum joint stability
• Frames and table platforms are wrapped in high grade polyurethane foam, custom shaped, fabricated, and slip-covered
SEAT CONSTRUCTION
• Seat cushions are attached to frame and feature an 8-1⁄2" cushion constructed of an inner steel springcoil pack enveloped by high grade polyurethane foam
BACK CONSTRUCTION
• Back pillows are attached to back frame and feature a recycled polyester filled insert
• Back and seat cushions are attached but replaceable
ARM CONSTRUCTION
• Arms are wrapped in high grade polyurethane foam, custom shaped, fabricated and slip-covered
• Arms are connected to frame using 4 bolts per arm
UPHOLSTERY DETAILS
• Top stitch is a French seam and is offered in matching or contrasting thread colors, except on tables
• Comfort wrinkles on the seat and back cushions are an inherent part of the design
• Contrasting fabric available on all models, except tables
LEGS
• Wood square legs offered in all National seating finishes
• When specifying Brighton, Sonoma, and Natural finish, variation in color is acceptable due to the nature of wood characteristics
• Features 1" adjustable nylon leveling glides

CODE 02.ST.0001 Side Table

QTY 3

MFG / National Office Furniture
MODEL Footings X-Base CBV2119XBP

DIMENSIONS 24" Round x 19" H

FINISHES Architect shall select from manufacturers complete range of standard finishes.

DISTRIBUTION
123 CONFERENCE
207 KITCHEN / DINING

SPECIFICATION

TOP: Laminate surfaces shall be 1-3/16" HPL (high pressure laminate) and feature a softened 3mm PVC rim surface. Laminate shall be 13/ 16” HPL (high pressure laminate). Woodgrain laminates shall have a grain direction running left-to-right.
BASE: End height base shall be constructed with a of 2”diameter column with (4) "feet" in an X-shape.

CODE 02.ST.0002 Side Table, Soft Square

QTY 1

MFG / MODEL National Office Furniture
Footings X-Base CBV2119XBP(Soft Square)

DIMENSIONS 24" Square x 19" H

FINISHES

DISTRIBUTION
102 FIRST AID & TRIAGE

SPECIFICATION

TOP: Laminate surfaces shall be 1-3/16" HPL (high pressure laminate) and feature a softened 3mm PVC rim surface. Laminate shall be 13/ 16" HPL (high pressure laminate). Woodgrain laminates shall have a grain direction running left-to-right.
BASE: End height base shall be constructed with a of 2 "diameter column with (4) "feet" in an X-shape.

CODE 02.TT.0001 Training Tables

QTY 26

MFG / MODEL MityLite Linenless
Fixed Width

DIMENSIONS 18" W x 60" L x 29" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
103 MEET / TRAIN

SPECIFICATION

Frame: Powder Coated Aluminum
Table Top: Commercial-grade Laminate
Capacity: 2,000 lbs.
Sustainability: GREENGUARD® Certified
Warranty: 15 Year
Non-Marring Glides
Standard Ganging
Made in the USA

LEGS
Conference legs or offset conference legs are standard on all tables. Legs are extruded and fabricated from aluminum. Legs are equipped with stacking plugs and glides.

LEG MECHANISM
The folding mechanism is extruded and fabricated from aluminum. Mechanism is welded to the table's legs and fastened to table runners. Patent pending Leg-Lock mechanism holds the folded leg flat against the table when not in use.

CODE 02.TT.0001A Table Cart

QTY 4

MFG / MODEL MityLite RT Reveal Cart

DIMENSIONS 30.25" W x 44.25" H x 63" L

FINISHES Black Sand Powder Coat

DISTRIBUTION
103B TABLES / CHAIRS

SPECIFICATION

Frame: Steel
Finish: Black sand powder coat
Warranty: 12 Year
Casters: Non-marring wheels
Made in the USA
Reveal Table Compatability: Rectangle, Duo, Specialty, Mobile Buffet, Flip
7 Tables: 72" - 96"
5 Tables: 48" - 60"

CODE 03.TD.0001 Dining Table

QTY 1

MFG / Surfaceworks
MODEL Rapport T-Leg RPC.R.48144

DIMENSIONS 144" L x 48" W x 29" H

FINISHES Architect shall select from manufacturers complete range of standard finishes.

DISTRIBUTION
207 KITCHEN / DINING

SPECIFICATION

Table tops: Standard table tops are constructed with 1-1/8" M3 Industrial Grade 47# density particle board.
They are constructed with HPL (high pressure laminate) on the top side and a balanced backer on the bottom side for the greatest resistance to deflection.
Bolted/ Welded
Base: Column: 11-guage steel tube stock
Plate: 7-guage steel with a 11-gauge steel gusset for increased stability
Glide: 5/16-18 x 1/2" zinc stem w/ 1-7/8" Blk base Glide
Features: Removable .185" wire management panel T-base

CODE 03.VF.0005 5-Drawer Vertical File

QTY 16

MFG / Hon 210 Series
MODEL H215C.P.Q

DIMENSIONS 15" W x 26-1/2" D x 60" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
126 RECORDS STORAGE

SPECIFICATION

26-1/2" Case depth with 25 front-to-back filing inches per drawer. Two-drawer letter size files. Three-part, telescoping, steel ball-bearing suspension. Bright aluminum drawer pulls, label holders and thumb latch. Standard interchangeable core removable locks. Equipped with HON® "One Key" system. Baked enamel finish over rust-inhibiting phosphate pre-treatment. HON® Full Lifetime Warranty.

Number of Drawers: 5
Construction Type: Assembled
File Size Type: Letter
Brand: HON
Series Name: 310 Series
Warranty: Limited Lifetime
Material: Steel
Manufacturers Part Number: HON315PQ

CODE 04.BK.3628 2-Shelf Bookcases

QTY 5

MFG / Great Openings Trace
MODEL GBS 3628

DIMENSIONS 36" W x 13" D x 28" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
119 CHIEF
121 ADMIN ASSISTANT
213B DUTY OFFICER

SPECIFICATION

GENERAL: Double walled bookcase shall feature all welded steel frame construction. All front vertical edges shall be square. Bottom channels and bookcase top shall be 18 gauge steel. Back and side panels and side channels shall be 22 gauge steel. Outer side panels shall be flush with the sides of the bookcase top, so there will be no gap when installed side-by-side. Top shall be mechanically fastened so it may be replaced with a laminate top.
SHELVES: Shall be constructed with 18 gauge steel and shall be adjustable on 1/2" increments. Shelves shall each have a capacity of 140 pounds.
GLIDES: Bookcase shall be provided with leveling glides with 5/8" adjustment.

CODE 04.BK.3652 4-Shelf Bookcase

QTY 4 MFG / MODEL Great Openings Trace GBS 3652

DIMENSIONS 36" W x 13-7/16" D x 52" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
122 FIRE PREVENTION

SPECIFICATION

GENERAL: Double walled bookcase shall feature all welded steel frame construction. All front vertical edges shall be square. Bottom channels and bookcase top shall be 18 gauge steel. Back and side panels and side channels shall be 22 gauge steel. Outer side panels shall be flush with the sides of the bookcase top, so there will be no gap when installed side-by-side. Top shall be mechanically fastened so it may be replaced with a laminate top.
SHELVES: Shall be constructed with 18 gauge steel and shall be adjustable on 1/2" increments. Shelves shall each have a capacity of 140 pounds.
GLIDES: Bookcase shall be provided with leveling glides with 5/8" adjustment.

CODE 04.BK.3666 5-Shelf Bookcase

QTY 8 MFG / MODEL Great Openings Trace GBS 3666

DIMENSIONS 36" W x 13-7/16" D x 66" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
113 PAYROLL / ARSON
118 DEPUTY CHIEF
126 RECORDS STORAGE

SPECIFICATION

GENERAL: Double walled bookcase shall feature all welded steel frame construction. All front vertical edges shall be square. Bottom channels and bookcase top shall be 18 gauge steel. Back and side panels and side channels shall be 22 gauge steel. Outer side panels shall be flush with the sides of the bookcase top, so there will be no gap when installed side-by-side. Top shall be mechanically fastened so it may be replaced with a laminate top.
SHELVES: Shall be constructed with 18 gauge steel and shall be adjustable on 1/2" increments. Shelves shall each have a capacity of 140 pounds.
GLIDES: Bookcase shall be provided with leveling glides with 5/8" adjustment.

CODE 04.BK.4266 5-Shelf Bookcase

QTY 5 MFG / MODEL Great Openings Trace GBS 4266

DIMENSIONS 42" W x 13-7/16" D x 66" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
115 PERMITS / OIL BURNER
116 EMS / TRAINING
119 CHIEF

SPECIFICATION

GENERAL: Double walled bookcase shall feature all welded steel frame construction. All front vertical edges shall be square. Bottom channels and bookcase top shall be 18 gauge steel. Back and side panels and side channels shall be 22 gauge steel. Outer side panels shall be flush with the sides of the bookcase top, so there will be no gap when installed side-by-side. Top shall be mechanically fastened so it may be replaced with a laminate top.
SHELVES: Shall be constructed with 18 gauge steel and shall be adjustable on 1/2" increments. Shelves shall each have a capacity of 140 pounds.
GLIDES: Bookcase shall be provided with leveling glides with 5/8" adjustment.

CODE 05.FP.03FF 2-Drawer Pedestal File

QTY 2 MFG / MODEL Great Openings Trace EL 5109

DIMENSIONS 15-1/4" W x 21-7/8" D x 27-3/4" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
M101 OFFICE

SPECIFICATION

GENERAL: Pedestal shall have welded steel frame construction and reinforced vertical and horizontal channels. Top and side panel shall be 18-21 gauge cold rolled steel, outer panels and drawer bins shall be 22 gauge steel, drawer fronts shall be 20 gauge steel. Drawers shall feature full extension steel ball-bearing slides. Slides shall include "anti-rebound" and "quick disconnect" features.
DRAWERS: Drawer fronts shall include full width pull and rubber bumpers for quiet operation. Pedestals shall feature four leveing glides with 1-5/8" adjustment to ensure proper alignment and operation. Counterweight shall be included for stability.
LOCKS: Locks shall be keyed alike per room. Provide master key.

CODE 05.LF.0236 2-Drawer Lateral File

QTY 18 MFG / MODEL Great Openings Trace C401

DIMENSIONS 36" W x 18-1/4" D x 28-3/8" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
118 DEPUTY CHIEF
113 PAYROLL / ARSON
115 PERMITS / OIL BURNER
116 EMS / TRAINING
213B DUTY OFFICER
202 SHIFT SUPERVISOR
119 CHIEF
121 ADMIN ASSISTANT
131 WATCH ROOM

SPECIFICATION

GENERAL: File shall utilize welded steel frame construction and shall include reinforced vertical and horizontal channels. Top and side panels shall be 18-21 gauge cold rolled steel, outer panels and drawer bins shall be 22 gauge steel, and drawer fronts shall be 20 gauge steel.
DRAWER SLIDES: Shall be full extension steel ball-bearing slides. Slides shall include "anti-rebound" and "quick disconnect."
DRAWERS: Drawer fronts shall include rubber bumpers for quiet operation. Drawers shall feature full-width pulls.
GLIDES: Four leveling glides with adjustment.
LOCKS: Locks shall be keyed alike per room. Provide master key.

CODE 05.LF.0436 4-Drawer Lateral File

QTY 4 MFG / MODEL Great Openings Trace D103

DIMENSIONS 36" W x 18-1/4" D x 51-3/8" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

DISTRIBUTION
122 FIRE PREVENTION
202 SHIFT SUPERVISOR
213B DUTY OFFICER

SPECIFICATION

GENERAL: File shall utilize welded steel frame construction and shall include reinforced vertical and horizontal channels. Top and side panels shall be 18-21 gauge cold rolled steel, outer panels and drawer bins shall be 22 gauge steel, and drawer fronts shall be 20 gauge steel.
DRAWER SLIDES: Shall be full extension steel ball-bearing slides. Slides shall include "anti-rebound" and "quick disconnect."
DRAWERS: Drawer fronts shall include rubber bumpers for quiet operation. Drawers shall feature full-width pulls.
GLIDES: Four leveling glides with adjustment.
LOCKS: Locks shall be keyed alike per room. Provide master key.

CODE 05.MP.03BF 3-Drawer Mobile Pedestal

QTY 19 MFG / MODEL Great Openings Trace EL 1819

DIMENSIONS 15-1/4" W x 21-7/8" D x 24" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

SPECIFICATION

GENERAL: Pedestal shall have welded steel frame construction and reinforced vertical and horizontal channels. Top and side panel shall be 18-21 gauge cold rolled steel, outer panels and drawer bins shall be 22 gauge steel, drawer fronts shall be 20 gauge steel. Drawers shall feature full extension steel ball-bearing slides. Slides shall include "anti-rebound" and "quick disconnect" features.
DRAWERS: Drawer fronts shall include full width pull and rubber bumpers for quiet operation. Pedestals shall feature four 37 mm black casters, 2 locking and 2 non-locking. Counterweight shall be included for stability.
LOCKS: Locks shall be keyed alike per room. Provide master key.

DISTRIBUTION
116 EMS / TRAINING
118 DEPUTY CHIEF
119 CHIEF
121 ADMIN ASSISTANT
122 FIRE PREVENTION
113 PAYROLL / ARSON
115 PERMITS / OIL BURNER
131 WATCH ROOM
202 SHIFT SUPERVISOR
213B DUTY OFFICER
M101 OFFICE

CODE 06.BB.0001 XL Twin Bunk

QTY 8 MFG / MODEL Norix Protégé NextGen Steel Single Bed

DIMENSIONS 86-1/2" L x 39-1/2" W x 34-1/2" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

SPECIFICATION

CONSTRUCTION:
- 24-gauge tubular steel frame with decorative wood grain laminate headboard
- Adjustable Glide Kit

DISTRIBUTION
201 BUNK ROOM
210A BUNK ROOM
210B BUNK ROOM
211A BUNK ROOM
211B BUNK ROOM
212A BUNK ROOM
212B BUNK ROOM
213A BUNK ROOM

CODE 06.BB.0002 Nightstand

QTY 8 MFG / MODEL Norix Protégé Nightstand PROT700

DIMENSIONS 18" W x 18" D x 24-1/2" H

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

SPECIFICATION

CONSTRUCTION:
- 19-gauge steel
- high-impact density fiberboard and high pressure laminate top

DISTRIBUTION
210A BUNK ROOM
210B BUNK ROOM
211A BUNK ROOM
211B BUNK ROOM
212A BUNK ROOM
212B BUNK ROOM
213A BUNK ROOM
201 BUNK ROOM

CODE 06.MB.0001 Twin XL Murphy Bed

QTY 1

MFG / MODEL Murphy Wall-Beds
Build-a-Bed

DIMENSIONS 44-1/2" W x 85-1/16 H x 15-7/8" D

FINISHES Architect shall select from manufacturer's complete range of standard finishes.

SPECIFICATION

Vertical cabinet bed
Brushed Nickel Curved Handle & Round Knob
Standard 4" H x 3/4" baseboard notch

Mounting hardware

DISTRIBUTION
119 CHIEF

CODE 06.MB.0001A Twin XL Mattress

QTY 8

MFG / MODEL Clover Mattress w/ Twin XL 5.5" Standard Foundation

DIMENSIONS Dimensions:80"L x 39"W x 9"H
Foundation:80"L x 38"W x 5.5"H

FINISHES

SPECIFICATION

Quilt: Stretch Knit Cover
FR Fibers
1" Quilting Fibers featuring Copper, Silver & Gel
1/2" Poly foam 1.2LB
Comfort Layers: 2" Eco Fiber Pad
BELOW INNERSPRING
3/4" Eco Fiber Pad
All foam layers are Certi-Pur certified
Support System: Single Sided Sleep Surface
Offset spring design
13 3/4 Gauge steel - Twice tempered
T/286 F/396 Q/504 K/648
Full perimeter foam encasement
Mattress Type: Kids,Innerspring

DISTRIBUTION
201 BUNK ROOM
210A BUNK ROOM
210B BUNK ROOM
211A BUNK ROOM
211B BUNK ROOM
212A BUNK ROOM
212B BUNK ROOM
213A BUNK ROOM

CODE 06.MB.0001ANF Twin XL Mattress

QTY 1 MFG / MODEL Clover Mattress

DIMENSIONS Dimensions:80"L x 39"W x 9"H
Foundation:80"L x 38"W x 5.5"H

FINISHES

DISTRIBUTION
119 CHIEF

SPECIFICATION

Quilt: Stretch Knit Cover
FR Fibers
1" Quilting Fibers featuring
Copper, Silver & Gel
1/2" Poly foam 1.2LB
Comfort Layers: 2" Eco Fiber Pad
BELOW INNERSPRING
3/4" Eco Fiber Pad
All foam layers are Certi-Pur certified
Support System: Single Sided Sleep Surface
Offset spring design
13 3/4 Gauge steel - Twice tempered
T/286 F/396 Q/504 K/648
Full perimeter foam encasement
Mattress Type: Kids,Innerspring

CODE 07.AB.0001 50-Gallon Waste Bin

QTY 4 MFG / MODEL Rubbermaid 9W27 Brute 50-Gallon

DIMENSIONS 30" L x 24" W x 39-1/2" H

FINISHES

DISTRIBUTION
137 APPARATUS BAY
M102 APPARATUS BAY
139 ACCESSORY BAY

SPECIFICATION

Product Weight: 27.00 lbs.
Capacity 50 gal
Color: Gray
Material Type: Resin
Country of Origin: USA

CODE 07.AB.0002 50-Gallon Recycling Bin

QTY 4 MFG / MODEL Rubbermaid Brute 50-Gallon Recycling

DIMENSIONS 28-1/2" L x 23-1/2" W x 36-1/2" H

FINISHES

DISTRIBUTION
137 APPARATUS BAY
M102 APPARATUS BAY
139 ACCESSORY BAY

SPECIFICATION

Product Weight 21.80 lbs.
Capacity: 50 gal
Color: Blue
Material Type: Resin
Country of Origin: USA

CODE 07.AB.0003

Floor Pad Cart

QTY 5

MFG / MODEL Global Industrial T97952504

DIMENSIONS 30" W x 60" W

FINISHES

DISTRIBUTION
137 APPARATUS BAY
139 ACCESSORY BAY

SPECIFICATION

Superior performance at affordable prices. Flush 7/8" thick, kiln-dried and sealed deck is reinforced with cross battens for long life. Removable cross-braced tubular steel handle. Roll smoothly on 2 swivel, 2 rigid casters.
Wheel Diameter: 8 in.
Weight Capacity: 2400 lbs.
Deck Height: 10-3/4 in.
Weight: 100 lbs.
Assembly Required: Unassembled
Brand: Global Industrial
Deck Material: Wood Deck
Warranty: 1 yr.
Manufacturers Part Number: 952504
Handle Style: Cross-Braced
Wheel Type: Rubber

CODE 07.AB.0004

Floor Protection Pads

QTY 54

MFG / MODEL Sundance Mat 4 x 6 Ft x 3/4 inch Straight Edge Standard

DIMENSIONS 4' x 6' x 3/4" thick

FINISHES Pebbled Top, Black

DISTRIBUTION
137 APPARATUS BAY
139 ACCESSORY BAY

SPECIFICATION

Product Type: Mat
Material Type: Rubber
Product Edging: Straight
Thickness: 3/4 inch
Width: 4.00 feet
Length: 6.00 feet
SF per Item: 24.00
Weight: 100.00 lbs
Number of Pieces per Package Type: 25
Non Absorbent: Yes
Special Adhesives: No
Material Hardness: Shore A 75
Interlocking Connections: No
Made In Canada
Surface Finish: Pebble top
Surface Design: Solid color
Installation Method: Layout flat

CODE 07.ALL.0001 28-Quart Trash Can

QTY 25 MFG / MODEL Rubbermaid 2956 Wastebasket

DIMENSIONS 14-1/2" L x 10-1/2" W x 15" H

FINISHES Black

DISTRIBUTION

SPECIFICATION

All-plastic construction won't chip, rust or dent. Rolled rims add strength, and are easy to clean
Fits under standard-height desk

Capacity: 28 qt
Color: Black
Material Type: Resin
Country of Origin: USA

CODE 07.ALL.0007 7-Gallon Recycling Bin

QTY 22 MFG / MODEL Rubbermaid 2956-73 Deskside Recycling Container, Medium w/ Universal Symbol

DIMENSIONS 14-1/2" L x 10-1/2" W x 15" H

FINISHES Blue

DISTRIBUTION

SPECIFICATION

Capacity: 28 qt
Color: Blue
Material Type: Resin
Country of Origin: USA

CODE 07.ALL.0010 10-Gallon Recycling Container

QTY 3 MFG / MODEL Rubbermaid 2957

DIMENSIONS 15.255" L x 11.25" W x 20" H

FINISHES

DISTRIBUTION
103A KITCHENETTE
120 OFFICE SUPPORT
122 FIRE PREVENTION

SPECIFICATION

All-plastic construction won't chip, rust or dent. Rolled rims add strength, and are easy to clean
Fits under standard-height desk
Capacity: 41 qt
Color: Blue
Material Type: Resin
Country of Origin: USA

CODE 07.FS.0001 Walk Behind Floor Scrubber

QTY 1 MFG / MODEL Tennant T2

DIMENSIONS (Nominal) 44" L x 27-1/2" W (with squeegee) x 36-1/2" H

FINISHES

DISTRIBUTION
138 JANITOR

SPECIFICATION

Application: Indoor
Estimated Coverage/Productivity: Up to 7234 sq ft / 672 sq m
Estimated Run Time: Up to 3 hours
Main Down Pressure: Up to 50 lb / 23 kg
Power Source: Battery (12V, 105AH, Wet Battery; 12V, 70AH, Gel Battery)
Solution Tank Capacity: 7 gal / 26 L
Charger type: On-board
Cleaning Path: 17 in / 430 mm
Machine Type: Walk-Behind
Recovery Tank Capacity: 9.5 gal / 36 L
Sound Level: As low as 68 dBA
Squeegee Width: 27.4 in / 695 mm
Head Type: Disk

CODE 07.MS.1992 Waste Receptacle

QTY 18 MFG / MODEL Rubbermaid Slim Jim 1901992

DIMENSIONS 13-7/10" D x 18-1/10" W x 28-7/10 H

FINISHES Stainless Steel

DISTRIBUTION
132 READY ROOM
103A KITCHENETTE
120 OFFICE SUPPORT
104A TOILET
124 TOILET
125 TOILET
150 UNISEX TOILET
216 BUNK BATH
217 BUNK BATH
218 BUNK BATH
219 BUNK BATH
M106A TOILET
M106B TOILET
128 MENS
129 WOMENS
207 KITCHEN / DINING

SPECIFICATION

Capacity: 13 gal
Type: Hands Free Trash Can, Front Step
Package Quantity: 1
Brand: Rubbermaid Commercial
Lid Type: Flat Lid
Wheels: No
Material: Stainless Steel
Manufacturers Part Number: 1901992
Shape: Rectangle

CODE 07.OF.0001 Blueprint Rack

QTY 2 MFG / MODEL Interion by Global Industrial 298701

DIMENSIONS 29-46" D x 26-1/2" W x 45-65" H

FINISHES Sand

DISTRIBUTION
122 FIRE PREVENTION

SPECIFICATION

Easy-to-use vertical files provide ideal space-saving storage system for blueprints, drawings, plans and more. This model permits clamps to pivot for viewing and access. Each binder holds up to 100 sheets. The exclusive suspension system allows clamps to be slipped in and out of storage rack easily. Nylon tightening knobs and brass inserts eliminate the need for binding. Includes 4" label for easy identification. Constructed of durable anodized aluminum with a rugged Sand baked enamel finish. Includes 12 pivot brackets, and each rack accepts 12 clamps. Blueprint Clamps are sold separately in cartons of 6. Blueprint Mobile unit includes four 3" swivel casters, 2 rear locking. Accepts print sizes up to 60"L x 42"W.

CODE 07.OF.0001A Blueprint Rack Clamps (Set of 6)

QTY 2 MFG / MODEL Brookside Design PC642

DIMENSIONS 42" length for insert into blueprint pivot hangers

FINISHES Silver

DISTRIBUTION
122 FIRE PREVENTION

SPECIFICATION

Clamps for use with Interion Blueprint Rack

Package Quantity: 6 for a total of 12 clamps per blueprint rack
Material: Steel

CODE 07.OS.0001 Coffee Maker

QTY 2 MFG / MODEL Bunn Heat N' Brew Coffee Maker 10 cup

DIMENSIONS 16.3" H x 8.7" W x 9.7" D

FINISHES

DISTRIBUTION
103A KITCHENETTE
120 OFFICE SUPPORT

SPECIFICATION

- Programmable
- Capacity: 10 cups
- Auto Shut Off
- 3-year warranty

CODE 07.TR.0001 Reclining Patient Chair

QTY 1 MFG / MODEL Winco Extra Large Three-Position Recliner

DIMENSIONS 35"W x 49"H; Seat: 25"W x 22-1/2"H; Back: 31-1/2"H

FINISHES Color: Grey

DISTRIBUTION
102 FIRST AID & TRIAGE

SPECIFICATION

Extra-large, three-position chair with a 25"W seat width to accommodate larger patients. Webbed elastic suspension seating is durable and comfortable. Total-lock 5" steel casters prevent shifting and sliding. Built-in headrest and lumbar support. Dual fold-down side tables with recessed cup holders. Oversized footrest gives tall patients optimal foot support.

• 450-lb. capacity • Heavy-duty, powder-coated steel frame

CODE 07.TR.0002 Treatment Table

QTY 1 MFG / MODEL Clinton Industries 3020-30

DIMENSIONS 72" L x 30" W x 31" H

FINISHES Color: Warm Gray - 3WG

DISTRIBUTION
102 FIRST AID & TRIAGE

SPECIFICATION

- Powder-coated, all-steel frame, gray laminate shelf and an adjustable backrest
- Easy bolt-through assembly
- Paper dispenser included
- Adjustable leg levelers
- Seamless rounded corner top
- Heavyweight, knit-backed upholstery
- Padding: 2" firm foam padding (5 cm)
- Load Capacity: 450 lbs. load capacity under normal use (204 kg)
- Width: 30"

CODE 07.TR.0003 AED

QTY 2 MFG / MODEL Physio Control Lifepak 1000

DIMENSIONS 3.4" H x 9.2" W x 10.9" D

FINISHES N/A

DISTRIBUTION
102 FIRST AID & TRIAGE
131 WATCH ROOM

SPECIFICATION

All specifications are at 68°F (20°C) unless otherwise specified.
Waveform: Biphasic truncated exponential with voltage and duration compensation for patient impedance*.
Energy sequence: User configurable, 150 joules–360 joules. Default energy output settings are 200, 300, 360 joules. 360 joules for every shock thereafter.
Charge time: With new, nonrechargeable battery pack; 200 joules in less than 9 seconds (360 joules in less than 15 seconds).
3-Wire (Lead II) monitoring capability:
(If ECG display option purchased). Requires purchase of 3-wire (Lead II) monitoring cable and LIFE-PATCH® electrodes.
Device software: Field upgradeable.
Infant/Child reduced energy defibrillation electrodes: Reduces selected energy by a factor of 4. Intended for use only with children up to 8 years of age or 55 lbs (25 kg).
Safety classification: Internally powered equipment IEC 60601-1.
Electrical protection: Input protected against high voltage defibrillator pulses per IEC 60601-1.
*Voltage compensation is limited to the voltage that would result in delivery of 360 joules into 50 ohms.

CODE 07.TR.0004 Portable O2

QTY 1 MFG / MODEL Tri-Med M9 Cylinder w/ Bag

DIMENSIONS 8.5" L x 5.5" W x 15" H

FINISHES

DISTRIBUTION
102 FIRST AID & TRIAGE

SPECIFICATION

The entire system weighs only 5.5 Lbs. and is only 8.5" L x 5.5" W x 15" H.
Each M9 Cylinder holds 240 Liters, with a 1-8 LPM continuous flow regulator @ 2 LPM equals 2.1 Hours. A heavy duty shoulder carrying bag.
Cylinders are DOT 3AL and CTC 3AL approved.
With a Toggle Valve and a 2 Year Warranty.

CODE 07.TR.0005 Sharps Container

QTY 1 MFG / MODEL COVIDIEN Auto Drop Sharps Container

DIMENSIONS 7-1/4" H x 4-3/4 L x 6-1/2" W

FINISHES

DISTRIBUTION
102 FIRST AID & TRIAGE

SPECIFICATION

Capacity: 2.2 qt
Color: Red
Lid Type: Auto Drop
Material: Plastic
Rotor Opening
For Use With Sharps Disposal

CODE 08.DS.0001 Outdoor Dining Set

QTY 2 MFG / MODEL Polywood Lakeside 7-piece Farmhouse Dining Set

DIMENSIONS Arm Chair: 24.81" W x 34.25" H x 21.38" D; Side Chair: 18.18" W x 34.25" H x 21.38" D

FINISHES Teak

DISTRIBUTION
DECK

SPECIFICATION

Includes (4) Lakeside Dining Side Chairs, (2) Lakeside Dining Arm Chairs, and (1) Lakeside 37" x 72" Farmhouse Dining Table
Built to withstand a range of climates including hot sun, snowy winters, and strong coastal winds
Durable, all-weather lumber not prone to splinter, crack, chip, peel, or rot
20-year limited residential warranty; 3-year limited commercial warranty
Cleans easily with soap, water, and a soft bristle brush
UV protectant and color continuously throughout the HDPE material; requires no painting or waterproofing

CODE 09.CB.0001A Cylinder Wall Bracket

QTY 1 MFG / MODEL USA Safety GB110FS

DIMENSIONS 9" W x 2" D x 4" H

FINISHES

DISTRIBUTION
148 SCBA FILL

SPECIFICATION

This gas cylinder bracket is molded from reinforced polypropylene and can be adjusted to snugly support any gas cylinder from 4 to 12 inches in diameter. The cylinder bracket is first set to designated cylinder diameter using recessed set screws that lock in the width position. Safely support gas cylinders, including acetylene, argon, butane, carbon dioxide (CO2), helium, hydrogen and nitrogen cylinders. The cylinder support permanently mounts to a wall using fasteners. Includes both cylinder strap and security chain sets. The strap is made of 1.5-inch-wide by 54-inch-long woven polypropylene with steel cinch buckle. This cylinder bracket is made in the USA.
Gas cylinder bracket dimensions (WxDxH): 9" x 2" x 4". MPN: 35256 (previously G-110)

CODE 09.CB.0001B Cylinder Wall Bracket

QTY 2 MFG / MODEL USA Safety 4-Cylinder Wall Bracket #GB401FS

DIMENSIONS 48" W x 2.25" D x 4.25" H

FINISHES

DISTRIBUTION
153 O2 STORAGE

SPECIFICATION

This gas cylinder bracket holds four cylinders and is constructed of 11 Gauge hot rolled steel. The cylinder support's edges are protected with steel reinforced vinyl edge guarding to help maintain your gas cylinders and provide extra grip. Steel parts are sealed with polyester powder-coat paint to assure long service life and chemical resistance. Straps and cinch style buckles are chosen as primary means of support, as they enable the gas cylinders to be held tightly and securely against the cylinder brackets. Polypropylene support straps are 1.5 inch wide by 54 inches long with steel cinch buckles. They cylinder support holds cylinders from 4 to 12 inch diameter. Chain sets are optional and can be easily added as a second means of support. It ships parcel or freight for larger quantities. This cylinder bracket is made in the USA. Product Dimensions (WxDxH): 48" x 2.25" x 4.25". MPN: 35276 (previously G-401)

CODE 09.CC.0001 Cylinder Cart

QTY 1 MFG / MODEL Global Industrial WGB1461324

DIMENSIONS 18" D x 24" W x 39" H

FINISHES

DISTRIBUTION
148 SCBA FILL

SPECIFICATION

Bottle cart consists of open wire, chrome plated shelving uprighted on posts with casters. Two casters have foot operated brakes. Full length dividers separate shelves to hold SCBA bottles. Standard units available hold 16-42 bottles or can be custom designed to fit your specifications.
Wheel Size: 5"
Cylinder Size: 5" - 8" Dia.
Weight Capacity: 800 lbs
Gauge: 9 ga
Weight: 45 lbs
Assembly Required: Unassembled
Capacity: 12 Cylinders
Number of Fixed Shelves: 3
Type: Cart
Cylinder Type: SCBA
Brand: Groves Inc
Package Quantity: 1
Warranty: 5 yr
Material: Steel
Style: Mobile
Manufacturers Part Number: MBR-MP
Color Family: Silver
Wheel Type: (2) Swivel Casters & (2) Swivel/Brake Casters

CODE 09.CC.0002 Mobile O2 Cylinder Cart

QTY 1

MFG / USA Safety
MODEL GCMDE24SC

DIMENSIONS 34" W x 22" D x 35" H

FINISHES

DISTRIBUTION
154 EMS LOCAL STORAGE

SPECIFICATION

This 24 cylinder capacity oxygen and medical cylinder cart is capable of handling size D, E medical cylinders (typically 4.5" diameter). It moves on four ultra-quiet 4" casters utilizing rear swivel casters with break for exceptional handling. The cylinder slot openings are approximately 5" square. Cylinders are held 5.5" off of the ground. Handle height is approximately 35". The mobile cylinder cart is constructed from welded steel supports that are 14 gauge, 1" round, 1" square and 0.5" square. This cart is designed for the safe transport of small compressed gas cylinders like oxygen. The cart is powder coated green. This product is made in the USA. Product Dimensions (WxDxH): 34"x22"x35". Cylinders not included. MPN: MDE-24

CODE 09.NC.LNC5 Narcotics Cabinet

QTY 1

MFG / Lakeside
MODEL SKU #LNC-5

DIMENSIONS 30" H x 24" W x 10" D

FINISHES

DISTRIBUTION
154 EMS LOCAL STORAGE

SPECIFICATION

Double locks
Two keys per lock included
Powder coated steel
Hinges ship standard on side shown; door hinges can easily be switched in the field by turning cabinet upside down and flipping over shelves
Overall Dimensions: 30" H x 24" W x 10" D
Inside Dimensions: 29.9" H x 23.8" W x 9.8" D
Interior Shelving: 3 adjustable
Color: Beige
Manufacturer: Lakeside Manufacturing
Lock Type: Key
Country of Origin: United States of America

CODE 09.SC.3619 Antimicrobial Cabinet

QTY 2 MFG / MODEL Hallowell Antimicrobial Storage Cabinet 800 Series

DIMENSIONS 48" W x 78" H x 18" D

FINISHES

DISTRIBUTION
154 EMS LOCAL STORAGE
152 EMS DEPT STORAGE

SPECIFICATION

Cabinets feature 3-point positive locking and a chrome plated locking handle with built-in grooved key lock. Shelves are adjustable on 2" centers and have a triple flanged front for added strength (up to 250 lbs - uniformly distributed). All-welded frame assembly and factory hung reinforced doors ensure proper operation and fit.
Number of Adjustable Shelves: 4
Cabinet Style: Full Height
Handle Type: Lever
Construction Type: Assembled
Material: Steel
Style: Storage Cabinet
Shelf Capacity: 250 lbs
Number of Shelves: 4
Lock Type: Keyed Differently
Brand: Hallowell
Door Type: Solid
Series: Industrial
Warranty: 2 yr
Manufacturers Part Number: 825S18A-PL-AM
Color Family: Gray
Inside Height: 70-3/4 in
Inside Depth: 16 in
Thickness: 20 ga
Weight: 164 lbs
Inside Width: 45 in

CODE 09.TC.0001 13-Drawer Tool Storage Cabinet & Chest

QTY 1 MFG / MODEL Global Industrial T97535487

DIMENSIONS 26-3/8" W x 18-1/8" D x 52-9/16" H

FINISHES

DISTRIBUTION
135 WORK ROOM

SPECIFICATION

Caster Size: 5x2 in.
Number of Drawers: 13
Type: Chest & Roller Cabinet Combo
Slide Type: Ball Bearing
Brand: Global Industrial
Series: Industrial
Warranty: 1 yr
Material: Steel
Style: Top & Bottom
Manufacturers Part Number: 535487
Color Family: Red

CODE 09.UC.3352 Mobile Stainless Steel Utility Cart

QTY 1 MFG / MODEL ULine H-3352

DIMENSIONS 42" L x 24" W x 35" H

FINISHES

DISTRIBUTION
154 EMS LOCAL STORAGE

SPECIFICATION

All-welded, corrosion-resistant stainless steel.
Lipped shelves, 1 1/2" deep.
Shelves are 25" apart for supplies.
5" polyurethane casters: 2 swivel, 2 rigid.
1,200 lb. load capacity

CODE 09.WB.0001 Panel Leg Workbench

QTY 1 MFG / MODEL Global Industrial WG250230

DIMENSIONS

FINISHES

DISTRIBUTION
135 WORK ROOM

SPECIFICATION

All-welded, corrosion-resistant stainless steel.
Lipped shelves, 1 1/2" deep.
Shelves are 25" apart for supplies.
5" polyurethane casters: 2 swivel, 2 rigid.

CODE 09.WB.0001B Panel Leg Workbench Power Riser

QTY 1 MFG / MODEL Global Industrial WG254744

DIMENSIONS 10-1/2" D x 72" W x 12" H

FINISHES Steel; Color: Gray

DISTRIBUTION
135 WORK ROOM

SPECIFICATION

This riser adds space to any workbench. This steel riser comes with powder coat finish. Its 2" high backstop prevents items from falling. There are mounting holes to allow easy workbench installation.
Add On Type: Riser
Assembly Required: Yes
Type: Riser
Brand: Global Industrial
Material: Steel
Style: Standard Riser

CODE 09.WB.0001C Panel Leg Workbench Steel Drawer

QTY 1 MFG / MODEL Global Industrial WG606964

DIMENSIONS 23-7/8" D x 18-1/4" W x 5-3/8" H

FINISHES Steel; Color: Gray

DISTRIBUTION
135 WORK ROOM

SPECIFICATION

Standard Workbench Drawer
Drawer can be mounted on either side of workbench and features the following:
All steel construction
Padlock hasp
Safety stop
Inside width inches: 18
Inside depth inches: 23-1/2
Inside width height: 5-1/4
Add On Type: Drawer
Assembly Required: No
Type: Drawer
Brand: Global Industrial
Material: Steel
Style: 5-3/8"H Standard Drawer

CODE 09.WB.0002 Mobile Adjustable Height Workbench

QTY 2 MFG / MODEL Global Industrial T97183149A

DIMENSIONS 30" D x 48" W x 36-43" H

FINISHES

DISTRIBUTION
135 WORK ROOM
M104 WORK ROOM

SPECIFICATION

Wheel Diameter: 5 in
Top Thickness: 1-3/4 in
Weight Capacity: 800 lbs
Leg Type: Adjustable
Assembly Required: Yes
Edge Type: Square
Wheel Material: Polyurethane
Type: Mobile Standard Workbench
Top Material: Maple Butcher Block
Brand: Global Industrial
Leg Style: C-Channel Leg
Material: Steel
Manufacturers Part Number: 183149A
Color Family: Gray
Wheel Type: Locking

CODE 09.WB.0003 Steel Top Workbench

QTY 2 MFG / MODEL Uline H-1222-STEEL

DIMENSIONS 30" D x 48" W x 36-43" H

FINISHES Top: Maple; Frame: Steel; Color: Gray

DISTRIBUTION
M103 FIRE ALARM & TRAFFIC
M104 WORK ROOM

SPECIFICATION

Easily transport your workbench where you need it. 1-3/4" thick kiln-dried maple top with mineral oil protectant and standard square edge. Height adjustable work benches maintain a proper work height. 13-gauge C-Channel Legs are reinforced with cross bracing for extra strength and rigidity. Mobile work bench legs feature removable duplex knock-outs to accept electrical outlets (not included). Finished in scratch resistant gray powder coat. Mobile benches are easy to move on 5" casters (2 rigid, 2 swivel with brakes.)
Leg Type: Adjustable
Assembly Required: Yes
Edge Type: Square
Wheel Material: Polyurethane
Wheel Type: Locking
Type: Mobile Standard Workbench
Top Material: Maple Butcher Block
Brand: Global Industrial
Leg Style: C-Channel Leg
Material: Steel

CODE 10.BF.CFS5 3-Bottle Fill Station

QTY 1 MFG / MODEL Bauer CFS5.5-3S/SF/TM Containment Fill Station

DIMENSIONS 41" x 21" x 57.25"

FINISHES

DISTRIBUTION
148 SCBA FILL

SPECIFICATION

- Model CFC5.5/3S
- 3-Position, Remote Fill, Dual Function SCBA Fill Station
- Dual function, top mount, 4 bank cascade panel and air direction valve
- Vendor-provided training of unit and overall system
- Includes uncrating, set-up, delivery to project site and air quality test training; All electrical needs will be by Oth

CODE 10.CC.0001 SCBA Compressor

QTY 1 MFG / MODEL Bauer Verticus VAC13H-E3

DIMENSIONS

FINISHES

DISTRIBUTION
222 COMPRESSOR

SPECIFICATION

- Model VAC13H-E3 - VERTICUS
- 3-Phase, 10 Hp motor
- Stainless Steel tubing (run up to and across all ceilings or clamped to b/steel beams) from compressor location to fill station location.
- Vendor-provided training of unit and overall system
- Includes uncrating, set-up, delivery to project site and air quality test training; All electrical needs will be by Others

CODE 10.CC.0002 SCBA Compressor CO Monitor

QTY 1

MFG / MODEL Bauer GT/CO/III

DIMENSIONS

FINISHES

DISTRIBUTION
222 COMPRESSOR

SPECIFICATION

- Model: GT/CO/III
- Factory Installed in Verticus Compressor
- Vendor-provided training of unit and overall system
- Includes uncrating, set-up, delivery to project site and air quality test training; All electrical needs will be by Others

CODE 10.CM.RFID Fill Station RFID

QTY 1

MFG / MODEL Bauer RFID-Pro Cylinder Management System

DIMENSIONS

FINISHES

DISTRIBUTION
148 SCBA FILL

SPECIFICATION

- Bauer RFIDPro handheld scanning device (for up to 99 tanks)
- Bauer RFID tag retrofit kit (for 99 cylinders)
- 2-Year renewable Wireless Subscription
- Vendor-provided training of unit and overall system, including demonstration on SCBA cylinder report generation

Includes uncrating, set-up, delivery to project site and air quality test training; All electrical needs will be by Others

CODE 10.CS.0001 SCBA Cascade Cylinder Storage System

QTY 1

MFG / MODEL Bauer ASME 6K-4 + RCK-0037 (2 pack)

DIMENSIONS

FINISHES

DISTRIBUTION
222 COMPRESSOR

SPECIFICATION

- ASME6K-4 + RCK-0037 (2 pack)
- ASME 6000 PSIG Storage Tanks
- Vertical Configuration
- Storage Type: BANK
- Vendor-provided training of unit and overall system
- Includes uncrating, set-up, delivery to project site and air quality test training; All electrical needs will be by Others

CODE 10.RR.0001 Remote Reel

QTY 1 MFG / MODEL Bauer HR/REL-9/N-C

DIMENSIONS

FINISHES

DISTRIBUTION
148 SCBA FILL

SPECIFICATION

- Model HR/REL-9/N-C
- 100-foot long 6000psi line
- Stainless Steel tubing (run up to and across all ceilings or clamped to b/steel beams) from reel location back to fill station location.
- Vendor-provided training of unit and overall system
- Includes uncrating, set-up, delivery to project site and air quality test training; All electrical needs will be by Others

CODE 10.RS.0001 Remote Start

QTY 1 MFG / MODEL Bauer ASY-1069

DIMENSIONS

FINISHES

DISTRIBUTION
148 SCBA FILL

SPECIFICATION

- Model ASY-1069
- For use w/Verticus Compressor & CFS5.5/3S Fill Station
- Touch Screen Display w/Emergency Stop Button
- Vendor-provided training of unit and overall system
- Includes uncrating, set-up, delivery to project site and air quality test training; All electrical needs will be by Others

CODE M01.AH.0001 Antifreeze Handler

QTY 1 MFG / MODEL Gray AH-15

DIMENSIONS 30" Diameter; 9" H

FINISHES Green

DISTRIBUTION
M105 STORAGE

SPECIFICATION

Help keep your shop clean and free from slippery spills, with a simple, convenient way to capture and evacuate antifreeze from vehicles. The Gray® Portable Antifreeze Transfer Tank is a spill-resistant air-pressurized closed system that runs on shop air; no pumps required. It features a manual airtight seal and controlled fluid flow valve to help you easily transport the anti-freeze with no worries about spillage. The unit can be easily rolled around the shop on its 3 swivel casters, and the low-profile design fits easily under most vehicles and between stands for easy removal. Stands up for storage to save valuable space.
Hose Included
Discharge Hose Length: 10 ft
Air Input Range: Self-Regulated to 12 psi
Material: Steel
Maximum Air Input Pressure: 12 psi
Method of Discharge: With Shop Air
Pump Type: No Pump

CODE M01.CR.0001 Cable Reel Rack

QTY 1 MFG / MODEL Stromberg CR4836120

DIMENSIONS 48" W x 36" D x 120" H

FINISHES

DISTRIBUTION
M103 FIRE ALARM & TRAFFIC

SPECIFICATION

Three beams per unit.
2,000 lbs. capacity per pair of axle brackets.
Heavy duty - adjustable

CODE M01.CS.0032 SCBA Cylinder Storage

QTY 3 MFG / MODEL Geargrid Mini Mobile 02 Cylinder System

DIMENSIONS 50" W x 20" D x 59" H

FINISHES

DISTRIBUTION
M108 SCBA STORAGE

SPECIFICATION

Frame: Heavy-duty 1-¼” steel tubing
Side & Back Grids: High-strength ¼” steel wire, 3″ x 3″ square grid pattern
Shelves: High-strength ¼” steel wire, adjustable in 3″ increments. Hose, SCBA, flat or O2 options available
Casters: Locking casters handle up to 250 lbs. each
Finish: Super Durable TGIC powder coat
Colors: 7 standard colors
Shipping: Ships knocked down for ease of handling and reduced shipping costs
Assembly: With simple tools it’s fast and easy

CODE M01.DD.0001 2-Drum Drip Deck

QTY 2

MFG / MODEL PIG Poly Drip Deck PAK565

DIMENSIONS 26" W x 52" L x 5.75" H

FINISHES

DISTRIBUTION
M105 STORAGE

SPECIFICATION

The strongest drip decks you can buy won't buckle or bow. Guaranteed for life.
Low-profile 5.75"H design is easy to load or unload; pumps and funnels are easy to access
Molded-in sump catches leaks, drips and spills to help keep your storage areas clean and safe
Low-density polyethylene (LDPE) construction resists UV rays, rust, corrosion and most chemicals
Textured grating adds traction and lifts out for easy sump access
Translucent white sidewalls allow easy visual inspection
Dimensions: 26" W x 52" L x 5.75" H
Recycled Content: 43% Post-Industrial Recycled Polyethylene
Load Capacity UDL: 3000 lbs.
Sump Capacity: 22 gal.
Brand: PIG
Drain: None
Color: Black/White
Double-Stackable Unit: No
Grates (1) 48" L x 24" W Grate
Holds (2) 55 gal. Plastic or Steel Drums
Use With Flammables: No
Sold as 1 each
Weight: 40 lbs.
Composition: Sump - Polyethylene (LDPE) w/ UV Inhibitor; Grate - Polyethylene

CODE M01.DJ.0001 Portable Drum Jack

QTY 2

MFG / MODEL Vestil DRUM-55-36

DIMENSIONS

FINISHES

DISTRIBUTION
M105 STORAGE

SPECIFICATION

Item#: 856427
Brand: Vestil
Manufacturer's Warranty: 1 month parts/no labor
Ship Weight: 161.0 lbs
Capacity (lbs.): 500
Material: Steel
Drum Size (gal.): 55
Product Type: Drum jack
OSHA Approved: Yes
Wheel Size (in.): 6 x 1 1/2 (front) 3 x 1 1/2 (rear)
Wheel Type: Rigid, swivel

CODE M01.FA.0001 Desk

QTY 1

MFG / MODEL Alera Steel Double Pedestal Desk - T9AB1144836

DIMENSIONS 60" W x 24" D x 29-1/2" H

FINISHES Walnut / Black

DISTRIBUTION
M103 FIRE ALARM & TRAFFIC

SPECIFICATION

Durable laminate top with square edge is scratch- and stain-resistant.
Powder-coated steel frame helps reduce scratches.
Full-extension file drawers with telescoping ball bearing slides accommodate hanging files.
Box drawers with dividers operate on steel roller suspension.
Aluminum drawer handles.
Modesty panel for privacy.
Chrome-plated 1″ square tubular steel legs with adjustable levelers.
Center drawer sold separately.

Durable laminate top with square edge is scratch- and stain-resistant. Steel frame has a powder coated finish to help reduce scratches. Full-extension file drawers with telescoping ball bearing slides accommodate hanging file folders. Box drawers with dividers operate on steel roller suspension. Modesty panel for privacy. Chrome-plated 1″ square tubular steel legs with adjustable levelers.

Pedestal Count: 2
Drawer Configuration: Left: Box/File; Right: Box/File
Drawer Quantity: 4
Edge Detail Profile: Square Edge
Base Material: Steel
Top Material: Woodgrain Laminate
Top Thickness: 1″
Pedestal Types: 3/4-Height
Compliance Standards: Meets or exceeds ANSI/BIFMA Standards

CODE M01.OH.0001 Oil Handler

QTY 1

MFG / MODEL Gray OH-15

DIMENSIONS 30" D x 9" H

FINISHES

DISTRIBUTION
M105 STORAGE

SPECIFICATION

Capacity: 15 gal
Color: Red
Hose Included: Yes
Discharge Hose Length: 10 ft
Air Input Range: Self-Regulated to 12 psi
Includes: (3) 3 in Casters, Anti-Splash Mat
Material: Steel
Maximum Air Input Pressure: 12 psi
Method of Discharge: With Shop Air
Pump Type: No Pump

CODE M01.PR.0001 Pipe Rack

QTY 1

MFG / MODEL Global Industrial WG245648

DIMENSIONS 39" D x 84" W x 81" H

FINISHES

DISTRIBUTION
M103 FIRE ALARM & TRAFFIC

SPECIFICATION

Inside Height: 10 in
Max Shelf Capacity: 1500 lbs. to 2000 lbs.
Weight: 253 lbs
Description: Single Sided
Assembly Required: Unassembled
Number of Compartments: 7
Brand: Vestil
Number of Levels: 6
Material: Steel
Manufacturers Part Number:BAR-R-84-S
Shelf Capacity: 2000 lbs
Color Family: Blue

CODE M01.UC.0001 Undercarriage Cleaning System

QTY 1

MFG / MODEL Mosmatic Hurricane High Lift Model # TUW-520

DIMENSIONS 48" L x 23" W x 10" H

FINISHES

DISTRIBUTION
M102 APPARATUS BAY

SPECIFICATION

- Easily Cleans The Underside Of 10" Clearance & Up Vehicles
- Flush salt, mud, & debris from cars, trucks, & farm equipment
- Stainless Steel INOX Components
High Quality, Long Lasting Swivel Reinforced with self lubricating, stainless steel ball bearings; Specially designed for high revolutions ensuring durability
21" Turbo Rotary Arm With 2 Stabilizer Spray Heads & Riser
Counterbalanced & precisely equilibrated to prevent vibrations
Rotor arm has two 1/8"NPTF nozzles with size 3 orifice
Cleans underneath vehicles with 9.1" or more clearance
Relax-Action Trigger
Ergonomic design & let-off at top of trigger pull for comfort
Stainless Steel Wheels
Two 4" regular wheels & one 2.25" castor wheel manuever easily
Can Be Used With Hot Or Cold Water
Maximum pressure up to 4000 PSI; 3/8" inlet
Stainless Steel Guard Plate Protects the swivel & nozzle from falling dirt & fouling

CODE M01.WR.0001 Wheel Ramps

QTY 1 MFG / MODEL Gray PTRW-20

DIMENSIONS 15" W x 51" L

FINISHES

DISTRIBUTION
M105 STORAGE

SPECIFICATION

Sold by the Pair
Item: Truck Ramps
Type: Wide Portable
Load Capacity: 20 ton
Height: 9 in
Width: 15 in
Length: 51 in
Material: Steel

CODE M01.WR.0001S Mesh Work Stool

QTY 1 MFG / MODEL ULine H-5498

DIMENSIONS 19" W x 17" D x 24"-34" H

FINISHES Black

DISTRIBUTION
M104 WORK ROOM

SPECIFICATION

Padded, adjustable armrests.
Adjustable seat height and footring.
Mesh upholstered fabric seat.
Optional casters provide mobility.
Mesh Work Stool - 3 1/2" thick molded foam seat. Chrome footring.
Deluxe Mesh Work Stool - 4" thick molded foam seat. Oversized seat and backrest with adjustable lumbar support.

CODE M01.WR.0002 Flammable Cabinet

QTY 3 MFG / MODEL Global Industrial Part # 298541

DIMENSIONS 43" W x 18" D x 65" H

FINISHES Steel, Yellow

DISTRIBUTION
135 WORK ROOM
M103 FIRE ALARM & TRAFFIC
M104 WORK ROOM

SPECIFICATION

2 adjustable shelves, each with 350 lb. capacity
45 gal capacity
2 doors

Global™ flammable cabinets meet or exceed the NFPA Flammable Liquid Code #30 and the OSHA standard 1910.106 for storage of class I, II and III liquids. FM approved. All-welded construction provides additional strength and 18 gauge cabinet with 14 gauge doors offers additional fire protection. The double-walled design of these flammable cabinets allows 1-1/2" insulating air space and dual 2" air vents that connect to exhaust system to maintain safe temperatures. Built-in grounding connector and leveling feet. 350 lb. capacity shelves adjust easily on 2-1/2" centers.

Doors are equipped with full length piano hinges and feature a spill-proof sill, a flush paddle handle with 3 point latching and a highly visible warning label. This Manual Close Door model does not close automatically - doors will only latch when they are manually closed. Flush door handle prevents passersby from catching or banging.

CODE M01.WR.0003 Bench Grinder

QTY 1 MFG / MODEL DeWalt DW758

DIMENSIONS 17-3/4" H x 12-5/8" L x 10-3/4" W

FINISHES

DISTRIBUTION
M104 WORK ROOM

SPECIFICATION

For Max. Wheel Dia.: 8 in
Grinding Wheel Grit: 36/60
Arbor Size: 5/8 in
Dust Management: Yes
Lights Included: No
Application: Large Grinding
Current: 4.2A
Dust Collection Port Size: 2 1/2 in
Duty: Heavy Duty
Features Adjustable Tool Resets, Precision-Machined Aluminum Tool Rests to Accurately Position Work, Rear Exhaust Ports in Wheel Guards
Frequency: 60 Hz
Horsepower: 3/4
Housing Material: Cast Iron
Includes 36G Wheel, 60G Wheel, Eye Shield, Spark Deflector, Tool Rest
Max. Wheel Speed: 3,600 RPM
Phase: 1
Standards: CSA Certified, UL Listed
Voltage: 120V
Wheel Distance: 12 1/2 in

CODE M01.WR.0004 Drill Press

QTY 1 MFG / MODEL Delta 18-900L

DIMENSIONS

FINISHES

DISTRIBUTION
M104 WORK ROOM

SPECIFICATION

The first professionally featured Drill Press designed with the woodworker in mind. The patented oversized woodworker's table bevels and tilts for compound drilling operations. This Drill Press also features T-slots for clamping and a removable center insert for through-table drilling.

Auto-tensioning belt drive system allows for fast and easy speed changes while maximizing transmission efficiency with consistent belt tension and motor alignments
Full 6 in. quill stroke for deeper drilling applications and best-in-class capacity
Oversized woodworker's table with patented design bevels 0-degree 90-degree left and right, tilts forward 0-degree to 48-degree, features t-slots for clamping, and a removable center insert for through-table drilling
Micro-adjustable depth stops and independent depth scale allows the user to zero the scale and set up for repetitive drilling, quickly and easily
#2 morse taper spindle and #3 morse chuck taper
Full 6" quill travel
Micro adjustable depth stops and depth scale for repetitive drilling
Fully adjustable twin laser projects a bright red cross hair at drill bit contact on work piece
Flexible led light illuminates work surface
large non-tip base for stability

CODE M01.WR.0005 Oil Filter Crusher

QTY 1 MFG / MODEL Gray QP-50

DIMENSIONS 69-1/2" H x 15" W

FINISHES

DISTRIBUTION
M104 WORK ROOM

SPECIFICATION

The QP-50 heavy duty Quickpack® spin-on oil filter crusher provides automotive filter crushing. The QP-50 is 100% air operated for long lasting, maintenance-free operation. The filter crusher's removable catch basin allows the crusher to be easily cleaned. The interlocking feature prevents the door from opening until crushing is complete. Gray Manufacturing's oil filter crusher includes the mounting stand.

Air Operated
Frame Capacity (Tons): 11 ton
Steel Frame
Includes Mounting Stand

CODE M01.WR.0006 20-Gallon Parts Washer

QTY 1 MFG / MODEL Eastwood 14293

DIMENSIONS Overall: 30" W x 21" D X 34-1/2" H; Tank Size: 28" W x 18" D x 8" H

FINISHES

DISTRIBUTION
M104 WORK ROOM

SPECIFICATION

Welded steel construction
Removable work shelf
20-gal. tank capacity; 12-gal. cleaning solution capacity
Includes parts bin and flow-through brush
Pump circulates non-corrosive, water-based cleaning solution at 1 gallon per minute.
Rugged welded steel parts washer features a large removable component shelf plus small removable parts basket. Ideal for cleaning small or large parts. Flexible nozzle lets user spray fluid on work piece. The included flow through brush is perfect for removing tough grease and dirt off the part. Fusible link automatically closes lid in case of fire. Tank capacity is 20 gallons with a water-based solution capacity of 12 gallons. Tank has drain hole with plug. Lower shelf can hold tools and other must have items.
Input Power Requirements: 110-120vAC, 60 Hz, 10-amp circuit
Power Cord Length: 6' grounded
Drain Plug Thread Size: M14 x 12
Drain Plug O-Ring Size: 18×3.1
Thickness: 0.040" (1.0mm)

CODE M01.WR.0007 25-Ton Shop Press

QTY 1 MFG / MODEL Gray SP-25

DIMENSIONS

FINISHES

DISTRIBUTION
M104 WORK ROOM

SPECIFICATION

Capacity: 50,000 lb 22,679.62 kg
Cylinder Stroke: 6 1/4″ 15.88 cm
Weight: 510 lbs 231.33 kg
Adjustments: 4 1/4″ Increments 10.80 cm Increments
Overall Foot Print: 40 1/2″ x 28″

CODE M01.WR.0008 Tire Changer

QTY 1 MFG / MODEL Hunter TC39

DIMENSIONS 55" W x 72" H x 58" D

FINISHES

DISTRIBUTION
M104 WORK ROOM

SPECIFICATION

Mount / Demount Tool: Polymer Standard lever mount head
Clamping Type: Center w/ Quick Clamp and Cam Plate
Bead Loosening Type: Upper & Lower Rollers (Shovel Optional)
Match Mounting Capable: Yes
Adjustable Clamping Height: Yes, 3 position
Rim Diameter Range: 10-26 in.
Maximum Tire Diameter: 46 in.
Maximum Wheel Width: 19 in.
Drive Speed: Fully Variable, 0-14 RPM Clockwise; Single Speed, 7 RPM Counterclockwise
Drive Torque: 867 ft-lb (1175 N-m)
Wheel Lift Capacity: (if equipped) 176 lbs (80 kg)
Electrical Circuit Requirements: 208-230V, 6A, 50/60Hz; 1 ph NEMA 20 amp plug, L6-20P
Air Supply Requirements: 115-145 psi (8-10 bar)
Approximate Air Consumption: 4 CFM (110 Liters/Minute)

CODE M01.WR.0009 13-Drawer Tool Storage Cabinet

QTY 2 MFG / MODEL Global Industrial WG535653

DIMENSIONS 42-3/8" W x 18" D x 38-5/8" H

FINISHES Red

DISTRIBUTION
M104 WORK ROOM
M103 FIRE ALARM & TRAFFIC

SPECIFICATION

Heavy gauge steel body
Durable powder coat red finish
Raised edges on 3 sides to retain contents
High security lock with 2 keys secures all drawers
Aluminum drawer pull handles
Snap-in ball bearing slides for smooth operation under heavy loads
Heavy duty tubular side handle for easy steering
Screwdriver tray/storage area
6" x 2" Roller bearing casters (2 swivel, 2 swivel with brakes)
Foam drawer liners

Number of Drawers: 13
Type: Roller Cabinet
Slide Type: Ball Bearing
Brand: Global Industrial
Series: Industrial
Warranty: 1 yr
Material: Steel
Style: Bottom
Color Family: Red

CODE M01.WR.0010

Wheel Balancer

QTY 1

MFG / MODEL Hunter SmartWeight Pro

DIMENSIONS

FINISHES

DISTRIBUTION
M104 WORK ROOM

SPECIFICATION

20 in. Max Width
30 in. Max Rim Diameter
Up to 38 in. Max Tire Diameter
Up to 175 lbs. Maximum Tire Weight
Power Requirements: 208-240V, 3 amp, 50/60 Hz, 1 ph (NEMA 20 amp plug, L6-20P)
Air Supply Recommendations: 100-175 psi (7-12 bar)*
Approximate Air Consumption :4 CFM (110 Liters/Minute)
Internet Recommendations Hardwire or Wireless add on, 10+mbps up and down
Capacity:
Rim Width: (38 mm to 508 mm) 1.5 in to 20 in
Rim Diameter: (254 mm to 762 mm) 10 in to 30 in ǂ
ALU: (191 mm to 965 mm) 7.5 in to 38 in ǂ
Max. Tire Diameter: (965 mm) 38 in
Max. Tire Width: (508 mm) 20 in
Max. Tire Weight: (68 kg) 135 lbs
Imbalance Resolution: (± 1.0 g) 0.05 oz
Placement Accuracy: 512 positions, ± 0.35°
Balancing Speed: 150 rpm
Motor Programmable drive system and DC motor

CODE SB.OT.0001

Waste Oil Tank

QTY 1

MFG / MODEL Snyder Industries
Model No. 5700102N5703

DIMENSIONS 33" D x 51" H

FINISHES

DISTRIBUTION
SUPPORT BUILDING

SPECIFICATION

120 gallon waste oil tank, 33” diameter,51” height. Double wall weather resistant polyethylene construction for outdoor use with 120% containment capacity, complying with EPA used oil container standard CFR 49 279.22. Liquid access via one 2” male cam lock outlet with draw pipe and one 12” lockable manway / lid with strainer. Tank to be stenciled “Waste Oil Only”. Include tank gauge.

CODE SB.OT.0002

Oil & Antifreeze Waste Storage Disposal

QTY 1

MFG / Snyder Industries
MODEL Model No. 5700102N5703

DIMENSIONS 33" D x 51" H

FINISHES

DISTRIBUTION
SUPPORT BUILDING

SPECIFICATION

120 gallon waste oil tank, 33” diameter,51” height. Double wall weather resistant polyethylene construction for outdoor use with 120% containment capacity, complying with EPA used oil container standard CFR 49 279.22. Liquid access via one 2” male cam lock outlet with draw pipe and one 12” lockable manway / lid with strainer. Tank to be stenciled “Waste Antifreeze Only”. Include tank gauge.

BID FORM

* * * * * * * * * * I M P O R T A N T * * * * * * * * * *

Notice to Bidders: Read the Bid Documents in their entirety before pricing this job.

Company Name: _____

A. The Undersigned proposes to furnish and install certain Furnishings/Equipment for the Woburn Fire Headquarters, Woburn, MA in accordance with the accompanying Contract Documents prepared by DiNisco Design, Inc., 99 Chauncy Street, Suite 901, Boston, MA 02111, for the Contract Price(s) specified on the attached Bid Proposal Form(s).

B. This Bid includes Addenda number(s) _____

C. The contract price(s) will be per attached BID PROPOSAL FORMS.

D. The undersigned has completed and submits herewith the following documents:

- Bid Proposal completed and signed with unit cost and total cost of each item bid. If an Alternate is bid, proposal must provide alternate's Manufacturer/Model Number along with supporting document as indicated in 7.3.10 and 12. SAMPLES
- City of Woburn Bidder's Qualifications and References – Completed and signed
- Clerk's Certificate – Completed and signed
- Attestation Clause form – Completed and signed
- Certificate of Non-Collusion – Completed and signed
- Public Contracts – Debarment – Completed and signed.
- Conflict of Interest Certificate – Completed and signed
- W-9 – Completed and signed
- Bid Deposit – As indicated in Paragraph 10, INSTRUCTIONS TO BIDDERS

E. The Undersigned agrees that he has accepted the dates for Completion of the Work and that he hasread and incorporated in his bid price provisions for satisfying the requirements of the Invitation to Bid, Instructions to Bidders, the General and Special Conditions and each appropriate individual itemspecification.

F. The Undersigned hereby certifies that he is able to furnish labor where required, that he can work in harmony with all other elements of labor presently employed under the General Contract now in forcefor the construction of the project, and that he will comply fully with all laws and regulations applicableto awards made subject to M.G.L. Chapter 30B.

G. The undersigned further certifies under penalties of perjury that this bid or proposal has been madeand submitted in good faith and without collusion or fraud with any other person. As used in this certification, the work "person" shall mean any natural person, business, partnership, corporation, union, committee, club or other organization, entity, or group of individuals.

Date:_____ By_____
(Name and Title of Bidder)

_____
(Signature of Bidder)

_____
(Business Address)

_____
(City, State, Zip)

_____/_____
(Telephone) (Fax)

_____
(E-mail Address)

NOTE: If the bidder is a corporation, indicate state of incorporation under signature, and affix corporateseal; if a partnership, give full names and residential addresses of all partners; and if an individual, giveresidential address if different from business address. References required by the Invitation to Bid andthe Instructions to Bidders must be attached to this proposal.

CITY OF WOBURN
BIDDER'S QUALIFICATIONS AND REFERENCES FORM

Please list applicable references for ALL similar projects performed in the last five (5) years. Please use additional pages if required. All questions must be answered, and the data given must be clear and comprehensive. Please type or print legibly. This information will be utilized by the City for purposes of determining bidder responsiveness and responsibility with regard to the requirements and specifications ofthe Contract.

1. FIRM NAME _____

2. WHEN ORGANIZED _____

3. INCORPORATED?_____YES_____NO
DATE AND STATE OF INCORPORATION: _____

4. IS YOUR BUSINESS A **MBE**?_____YES__NO **WBE**?___YES__NO or **MWBE**?_____YES__NO

*5. LIST ALL CONTRACTS CURRENTLY ON HAND, SHOWING CONTRACT AMOUNT ANDANTICIPATED DATE OF COMPLETION:

_____

_____

_____

_____

_____

*6. HAVE YOU EVER FAILED TO COMPLETE A CONTRACT AWARDED TO YOU?
_____YES__NO, IF YES, WHERE AND WHY?

_____

_____

*7. HAVE YOU EVER DEFAULTED ON A CONTRACT?_____YES NO IF YES, PROVIDE DETAILS.

_____

_____

*8. LIST YOUR VEHICLES/EQUIPMENT AVAILABLE FOR THIS CONTRACT:

_____

_____

*9. IN THE SPACES FOLLOWING, PROVIDE INFORMATION REGARDING CONTRACTS COMPLETED BY YOUR FIRM SIMILAR IN NATURE TO THE PROJECT BEING BID. A MINIMUM OF FOUR (4) CONTRACTS SHALL BE LISTED. PUBLICLY BID CONTRACTS ARE PREFERRED, BUT NOT MANDATORY.

_____
PROJECT NAME:

_____
OWNER:

_____
CITY/STATE:

DOLLAR AMOUNT: $_____DATE COMPLETED: _____

PUBLICLY BID?_____YES_____NO

TYPE OF WORK?:

_____

CONTACT PERSON:_____PHONE #: (____)_____

CONTACT PERSON'S RELATION TO PROJECT?:

_____

(i.e., contract manager, purchasing agent, etc.)

_____
PROJECT NAME:

_____
OWNER:

_____
CITY/STATE:

DOLLAR AMOUNT: $_____DATE COMPLETED: _____

PUBLICLY BID?_____YES_____NO

TYPE OF WORK?:

_____

CONTACT PERSON:_____PHONE #: (____)_____

CONTACT PERSON'S RELATION TO PROJECT?:

_____

(i.e., contract manager, purchasing agent, etc.)

_____

PROJECT NAME:

_____

OWNER:

_____

CITY/STATE:

DOLLAR AMOUNT: $_____DATE COMPLETED: _____

PUBLICLY BID?_____YES_____NO

TYPE OF WORK?:

_____

CONTACT PERSON:_____PHONE #: (____)_____

CONTACT PERSON'S RELATION TO PROJECT?:

_____

(i.e., contract manager, purchasing agent, etc.)

_____

PROJECT NAME:

_____

OWNER:

_____

CITY/STATE:

DOLLAR AMOUNT: $_____DATE COMPLETED: _____

PUBLICLY BID?_____YES_____NO

TYPE OF WORK?:

_____

CONTACT PERSON:_____PHONE #: (____)_____

CONTACT PERSON'S RELATION TO PROJECT?:

_____

(i.e., contract manager, purchasing agent, etc.)

10. The undersigned certifies that the information contained herein is complete and accurate and herebyauthorizes and requests any person, firm, or corporation to furnish any information requested by the City in verification of the recitals comprising this statement of Bidder's qualifications and experience.

DATE:_____BIDDER:_____

SIGNATURE:_____

PRINTED NAME:_____TITLE _____

END OF SECTION

CLERK'S CERTIFICATE

At a duly authorized meeting of the Board of Directors of:

_____held on _____at which

all Voted that_____of this Company, be hereby authorized to execute contracts and bonds in the name and behalf of said Company, and affix its Corporate Seal thereto, and such execution of any contract of obligation on this Company's name on its

behalf by such_____under seal of thisCompany shall be valid and binding upon this Company.

A TRUE COPY,

ATTEST: (Clerk)

_____

PLACE OF BUSINESS:

_____

DATE OF THIS CONTRACT:

_____

I hereby certify that I am the Clerk of_____that

_____is the duly elected_____ of said Company, and that the above vote has not been amended or rescinded and remains in full force and effect as to the dateof this contract.

_____

Clerk Signature

CORPORATE SEAL:

ATTESTATION CLAUSE FORM

I certify, under penalties of perjury, that I, to my knowledge and belief, have filed all state tax returns and paid all state taxes required under Law.

_____

*Signature of Individual or Corporate Name/CorporateOfficer (Mandatory)

_____

Company Name

_____

** Social Security Number (Voluntary) or FederalIdentification Number

* Approval of a contract of other agreement will not be granted unless this certification clause is signed by the applicant.

** Your Social Security Number will be furnished to the Massachusetts Department of Revenue todetermine whether or not you have met tax filing or tax payment obligations. Providers who fail tocorrect their non-filing or delinquency will not have a contract or other agreement issued, renewed, or extended. This request is made under the authority of Massachusetts General Laws,Ch. 62C, Sec. 49A.

CERTIFICATE OF NON-COLLUSION

M.G.L. Chapter 40, Section 4B1/2, or Chapter 30, as applicable

Any person submitting a proposal for the sale, lease, or provision of equipment, supplies, or material or services to any government unit as defined in Section 4a shall on such proposal certifies as follows:

The undersigned certifies, under the penalties of perjury, that this bid or proposal is in all respectsbona fide, fair, and made and submitted in good faith and without collusion or fraud with any otherperson. As used in this certification, the word "person" shall mean any natural person, business, partnership, corporation, joint venture, union, committee, club, or other organization, legal entity, or group of individuals.

_____
Date

_____
Type or Printed Name of Person, Company or Corporation

_____
Authorized Official’s Signature

PUBLIC CONTRACTS – DEBARMENT

M.G.L. Chapter 29, Section 29F

The undersigned certifies, under penalties of perjury, that the said undersigned is not presently debarred from participating in public contracts in the Commonwealth of Massachusetts under the provisions of Chapter 29, Section 29F of the Massachusetts General Laws, or any other applicable debarment provision of any other Chapter of the General Laws, or any Rule or Regulation promulgated thereunder.

_____
Date

_____
Name of Company

_____
Address

_____
City, State, Zip Code

_____
Name of Bidder

_____
Signature

CONFLICT OF INTEREST CERTIFICATION

M.G.L. Chapter 268A, Section 19 or Section 20

I hereby certify, under the pains and penalties of perjury, that I am not a municipal employee of the City of Woburn, MA nor any members of my immediate family or partners are municipal employees of the City of Woburn, MA so as to cause a violation of Massachusetts General Laws, Chapter 268A, Section 19 or Section 20.

Signed under pains and penalties of perjury,

_____
Signature of Authorized Official

_____
Typed or Printed Name and Title of Signatory

_____
Date

Form **W-9**
(Rev. October 2018)
Department of the Treasury
Internal Revenue Service

Request for Taxpayer Identification Number and Certification

▶ **Go to *www.irs.gov/FormW9* for instructions and the latest information.**

Give Form to the requester. Do not send to the IRS.

Print or type. See Specific Instructions on page 3.

1 Name (as shown on your income tax return). Name is required on this line; do not leave this line blank.

2 Business name/disregarded entity name, if different from above

3 Check appropriate box for federal tax classification of the person whose name is entered on line 1. Check only **one** of the following seven boxes.

☐ Individual/sole proprietor or single-member LLC ☐ C Corporation ☐ S Corporation ☐ Partnership ☐ Trust/estate

☐ Limited liability company. Enter the tax classification (C=C corporation, S=S corporation, P=Partnership) ▶ _____

Note: Check the appropriate box in the line above for the tax classification of the single-member owner. Do not check LLC if the LLC is classified as a single-member LLC that is disregarded from the owner unless the owner of the LLC is another LLC that is **not** disregarded from the owner for U.S. federal tax purposes. Otherwise, a single-member LLC that is disregarded from the owner should check the appropriate box for the tax classification of its owner.

☐ Other (see instructions) ▶

4 Exemptions (codes apply only to certain entities, not individuals; see instructions on page 3):

Exempt payee code (if any) _____

Exemption from FATCA reporting code (if any) _____

(Applies to accounts maintained outside the U.S.)

5 Address (number, street, and apt. or suite no.) See instructions.

Requester's name and address (optional)

6 City, state, and ZIP code

7 List account number(s) here (optional)

Part I Taxpayer Identification Number (TIN)

Enter your TIN in the appropriate box. The TIN provided must match the name given on line 1 to avoid backup withholding. For individuals, this is generally your social security number (SSN). However, for a resident alien, sole proprietor, or disregarded entity, see the instructions for Part I, later. For other entities, it is your employer identification number (EIN). If you do not have a number, see *How to get a TIN*, later.

Note: If the account is in more than one name, see the instructions for line 1. Also see *What Name and Number To Give the Requester* for guidelines on whose number to enter.

Social security number

			–			–				

or

Employer identification number

		–							

Part II Certification

Under penalties of perjury, I certify that:

1. The number shown on this form is my correct taxpayer identification number (or I am waiting for a number to be issued to me); and
2. I am not subject to backup withholding because: (a) I am exempt from backup withholding, or (b) I have not been notified by the Internal Revenue Service (IRS) that I am subject to backup withholding as a result of a failure to report all interest or dividends, or (c) the IRS has notified me that I am no longer subject to backup withholding; and
3. I am a U.S. citizen or other U.S. person (defined below); and
4. The FATCA code(s) entered on this form (if any) indicating that I am exempt from FATCA reporting is correct.

Certification instructions. You must cross out item 2 above if you have been notified by the IRS that you are currently subject to backup withholding because you have failed to report all interest and dividends on your tax return. For real estate transactions, item 2 does not apply. For mortgage interest paid, acquisition or abandonment of secured property, cancellation of debt, contributions to an individual retirement arrangement (IRA), and generally, payments other than interest and dividends, you are not required to sign the certification, but you must provide your correct TIN. See the instructions for Part II, later.

Sign Here | **Signature of U.S. person** ▶ | **Date** ▶

General Instructions

Section references are to the Internal Revenue Code unless otherwise noted.

Future developments. For the latest information about developments related to Form W-9 and its instructions, such as legislation enacted after they were published, go to *www.irs.gov/FormW9.*

Purpose of Form

An individual or entity (Form W-9 requester) who is required to file an information return with the IRS must obtain your correct taxpayer identification number (TIN) which may be your social security number (SSN), individual taxpayer identification number (ITIN), adoption taxpayer identification number (ATIN), or employer identification number (EIN), to report on an information return the amount paid to you, or other amount reportable on an information return. Examples of information returns include, but are not limited to, the following.

- Form 1099-INT (interest earned or paid)
- Form 1099-DIV (dividends, including those from stocks or mutual funds)
- Form 1099-MISC (various types of income, prizes, awards, or gross proceeds)
- Form 1099-B (stock or mutual fund sales and certain other transactions by brokers)
- Form 1099-S (proceeds from real estate transactions)
- Form 1099-K (merchant card and third party network transactions)
- Form 1098 (home mortgage interest), 1098-E (student loan interest), 1098-T (tuition)
- Form 1099-C (canceled debt)
- Form 1099-A (acquisition or abandonment of secured property)

Use Form W-9 only if you are a U.S. person (including a resident alien), to provide your correct TIN.

If you do not return Form W-9 to the requester with a TIN, you might be subject to backup withholding. See What is backup withholding, *later.*

By signing the filled-out form, you:

1. Certify that the TIN you are giving is correct (or you are waiting for a number to be issued),

2. Certify that you are not subject to backup withholding, or

3. Claim exemption from backup withholding if you are a U.S. exempt payee. If applicable, you are also certifying that as a U.S. person, your allocable share of any partnership income from a U.S. trade or business is not subject to the withholding tax on foreign partners' share of effectively connected income, and

4. Certify that FATCA code(s) entered on this form (if any) indicating that you are exempt from the FATCA reporting, is correct. See *What is FATCA reporting,* later, for further information.

Note: If you are a U.S. person and a requester gives you a form other than Form W-9 to request your TIN, you must use the requester's form if it is substantially similar to this Form W-9.

Definition of a U.S. person. For federal tax purposes, you are considered a U.S. person if you are:

- An individual who is a U.S. citizen or U.S. resident alien;
- A partnership, corporation, company, or association created or organized in the United States or under the laws of the United States;
- An estate (other than a foreign estate); or
- A domestic trust (as defined in Regulations section 301.7701-7).

Special rules for partnerships. Partnerships that conduct a trade or business in the United States are generally required to pay a withholding tax under section 1446 on any foreign partners' share of effectively connected taxable income from such business. Further, in certain cases where a Form W-9 has not been received, the rules under section 1446 require a partnership to presume that a partner is a foreign person, and pay the section 1446 withholding tax. Therefore, if you are a U.S. person that is a partner in a partnership conducting a trade or business in the United States, provide Form W-9 to the partnership to establish your U.S. status and avoid section 1446 withholding on your share of partnership income.

In the cases below, the following person must give Form W-9 to the partnership for purposes of establishing its U.S. status and avoiding withholding on its allocable share of net income from the partnership conducting a trade or business in the United States.

- In the case of a disregarded entity with a U.S. owner, the U.S. owner of the disregarded entity and not the entity;
- In the case of a grantor trust with a U.S. grantor or other U.S. owner, generally, the U.S. grantor or other U.S. owner of the grantor trust and not the trust; and
- In the case of a U.S. trust (other than a grantor trust), the U.S. trust (other than a grantor trust) and not the beneficiaries of the trust.

Foreign person. If you are a foreign person or the U.S. branch of a foreign bank that has elected to be treated as a U.S. person, do not use Form W-9. Instead, use the appropriate Form W-8 or Form 8233 (see Pub. 515, Withholding of Tax on Nonresident Aliens and Foreign Entities).

Nonresident alien who becomes a resident alien. Generally, only a nonresident alien individual may use the terms of a tax treaty to reduce or eliminate U.S. tax on certain types of income. However, most tax treaties contain a provision known as a "saving clause." Exceptions specified in the saving clause may permit an exemption from tax to continue for certain types of income even after the payee has otherwise become a U.S. resident alien for tax purposes.

If you are a U.S. resident alien who is relying on an exception contained in the saving clause of a tax treaty to claim an exemption from U.S. tax on certain types of income, you must attach a statement to Form W-9 that specifies the following five items.

1. The treaty country. Generally, this must be the same treaty under which you claimed exemption from tax as a nonresident alien.

2. The treaty article addressing the income.

3. The article number (or location) in the tax treaty that contains the saving clause and its exceptions.

4. The type and amount of income that qualifies for the exemption from tax.

5. Sufficient facts to justify the exemption from tax under the terms of the treaty article.

Example. Article 20 of the U.S.-China income tax treaty allows an exemption from tax for scholarship income received by a Chinese student temporarily present in the United States. Under U.S. law, this student will become a resident alien for tax purposes if his or her stay in the United States exceeds 5 calendar years. However, paragraph 2 of the first Protocol to the U.S.-China treaty (dated April 30, 1984) allows the provisions of Article 20 to continue to apply even after the Chinese student becomes a resident alien of the United States. A Chinese student who qualifies for this exception (under paragraph 2 of the first protocol) and is relying on this exception to claim an exemption from tax on his or her scholarship or fellowship income would attach to Form W-9 a statement that includes the information described above to support that exemption.

If you are a nonresident alien or a foreign entity, give the requester the appropriate completed Form W-8 or Form 8233.

Backup Withholding

What is backup withholding? Persons making certain payments to you must under certain conditions withhold and pay to the IRS 24% of such payments. This is called "backup withholding." Payments that may be subject to backup withholding include interest, tax-exempt interest, dividends, broker and barter exchange transactions, rents, royalties, nonemployee pay, payments made in settlement of payment card and third party network transactions, and certain payments from fishing boat operators. Real estate transactions are not subject to backup withholding.

You will not be subject to backup withholding on payments you receive if you give the requester your correct TIN, make the proper certifications, and report all your taxable interest and dividends on your tax return.

Payments you receive will be subject to backup withholding if:

1. You do not furnish your TIN to the requester,

2. You do not certify your TIN when required (see the instructions for Part II for details),

3. The IRS tells the requester that you furnished an incorrect TIN,

4. The IRS tells you that you are subject to backup withholding because you did not report all your interest and dividends on your tax return (for reportable interest and dividends only), or

5. You do not certify to the requester that you are not subject to backup withholding under 4 above (for reportable interest and dividend accounts opened after 1983 only).

Certain payees and payments are exempt from backup withholding. See *Exempt payee code,* later, and the separate Instructions for the Requester of Form W-9 for more information.

Also see *Special rules for partnerships,* earlier.

What is FATCA Reporting?

The Foreign Account Tax Compliance Act (FATCA) requires a participating foreign financial institution to report all United States account holders that are specified United States persons. Certain payees are exempt from FATCA reporting. See *Exemption from FATCA reporting code,* later, and the Instructions for the Requester of Form W-9 for more information.

Updating Your Information

You must provide updated information to any person to whom you claimed to be an exempt payee if you are no longer an exempt payee and anticipate receiving reportable payments in the future from this person. For example, you may need to provide updated information if you are a C corporation that elects to be an S corporation, or if you no longer are tax exempt. In addition, you must furnish a new Form W-9 if the name or TIN changes for the account; for example, if the grantor of a grantor trust dies.

Penalties

Failure to furnish TIN. If you fail to furnish your correct TIN to a requester, you are subject to a penalty of $50 for each such failure unless your failure is due to reasonable cause and not to willful neglect.

Civil penalty for false information with respect to withholding. If you make a false statement with no reasonable basis that results in no backup withholding, you are subject to a $500 penalty.

Criminal penalty for falsifying information. Willfully falsifying certifications or affirmations may subject you to criminal penalties including fines and/or imprisonment.

Misuse of TINs. If the requester discloses or uses TINs in violation of federal law, the requester may be subject to civil and criminal penalties.

Specific Instructions

Line 1

You must enter one of the following on this line; **do not** leave this line blank. The name should match the name on your tax return.

If this Form W-9 is for a joint account (other than an account maintained by a foreign financial institution (FFI)), list first, and then circle, the name of the person or entity whose number you entered in Part I of Form W-9. If you are providing Form W-9 to an FFI to document a joint account, each holder of the account that is a U.S. person must provide a Form W-9.

a. **Individual.** Generally, enter the name shown on your tax return. If you have changed your last name without informing the Social Security Administration (SSA) of the name change, enter your first name, the last name as shown on your social security card, and your new last name.

Note: ITIN applicant: Enter your individual name as it was entered on your Form W-7 application, line 1a. This should also be the same as the name you entered on the Form 1040/1040A/1040EZ you filed with your application.

b. **Sole proprietor or single-member LLC.** Enter your individual name as shown on your 1040/1040A/1040EZ on line 1. You may enter your business, trade, or "doing business as" (DBA) name on line 2.

c. **Partnership, LLC that is not a single-member LLC, C corporation, or S corporation.** Enter the entity's name as shown on the entity's tax return on line 1 and any business, trade, or DBA name on line 2.

d. **Other entities.** Enter your name as shown on required U.S. federal tax documents on line 1. This name should match the name shown on the charter or other legal document creating the entity. You may enter any business, trade, or DBA name on line 2.

e. **Disregarded entity.** For U.S. federal tax purposes, an entity that is disregarded as an entity separate from its owner is treated as a "disregarded entity." See Regulations section 301.7701-2(c)(2)(iii). Enter the owner's name on line 1. The name of the entity entered on line 1 should never be a disregarded entity. The name on line 1 should be the name shown on the income tax return on which the income should be reported. For example, if a foreign LLC that is treated as a disregarded entity for U.S. federal tax purposes has a single owner that is a U.S. person, the U.S. owner's name is required to be provided on line 1. If the direct owner of the entity is also a disregarded entity, enter the first owner that is not disregarded for federal tax purposes. Enter the disregarded entity's name on line 2, "Business name/disregarded entity name." If the owner of the disregarded entity is a foreign person, the owner must complete an appropriate Form W-8 instead of a Form W-9. This is the case even if the foreign person has a U.S. TIN.

Line 2

If you have a business name, trade name, DBA name, or disregarded entity name, you may enter it on line 2.

Line 3

Check the appropriate box on line 3 for the U.S. federal tax classification of the person whose name is entered on line 1. Check only one box on line 3.

IF the entity/person on line 1 is a(n) . . .	THEN check the box for . . .
• Corporation	Corporation
• Individual • Sole proprietorship, or • Single-member limited liability company (LLC) owned by an individual and disregarded for U.S. federal tax purposes.	Individual/sole proprietor or single-member LLC
• LLC treated as a partnership for U.S. federal tax purposes, • LLC that has filed Form 8832 or 2553 to be taxed as a corporation, or • LLC that is disregarded as an entity separate from its owner but the owner is another LLC that is not disregarded for U.S. federal tax purposes.	Limited liability company and enter the appropriate tax classification. (P= Partnership; C= C corporation; or S= S corporation)
• Partnership	Partnership
• Trust/estate	Trust/estate

Line 4, Exemptions

If you are exempt from backup withholding and/or FATCA reporting, enter in the appropriate space on line 4 any code(s) that may apply to you.

Exempt payee code.

- Generally, individuals (including sole proprietors) are not exempt from backup withholding.
- Except as provided below, corporations are exempt from backup withholding for certain payments, including interest and dividends.
- Corporations are not exempt from backup withholding for payments made in settlement of payment card or third party network transactions.
- Corporations are not exempt from backup withholding with respect to attorneys' fees or gross proceeds paid to attorneys, and corporations that provide medical or health care services are not exempt with respect to payments reportable on Form 1099-MISC.

The following codes identify payees that are exempt from backup withholding. Enter the appropriate code in the space in line 4.

1—An organization exempt from tax under section 501(a), any IRA, or a custodial account under section 403(b)(7) if the account satisfies the requirements of section 401(f)(2)

2—The United States or any of its agencies or instrumentalities

3—A state, the District of Columbia, a U.S. commonwealth or possession, or any of their political subdivisions or instrumentalities

4—A foreign government or any of its political subdivisions, agencies, or instrumentalities

5—A corporation

6—A dealer in securities or commodities required to register in the United States, the District of Columbia, or a U.S. commonwealth or possession

7—A futures commission merchant registered with the Commodity Futures Trading Commission

8—A real estate investment trust

9—An entity registered at all times during the tax year under the Investment Company Act of 1940

10—A common trust fund operated by a bank under section 584(a)

11—A financial institution

12—A middleman known in the investment community as a nominee or custodian

13—A trust exempt from tax under section 664 or described in section 4947

The following chart shows types of payments that may be exempt from backup withholding. The chart applies to the exempt payees listed above, 1 through 13.

IF the payment is for . . .	THEN the payment is exempt for . . .
Interest and dividend payments	All exempt payees except for 7
Broker transactions	Exempt payees 1 through 4 and 6 through 11 and all C corporations. S corporations must not enter an exempt payee code because they are exempt only for sales of noncovered securities acquired prior to 2012.
Barter exchange transactions and patronage dividends	Exempt payees 1 through 4
Payments over $600 required to be reported and direct sales over $5,000[1]	Generally, exempt payees 1 through 5[2]
Payments made in settlement of payment card or third party network transactions	Exempt payees 1 through 4

[1] See Form 1099-MISC, Miscellaneous Income, and its instructions.

[2] However, the following payments made to a corporation and reportable on Form 1099-MISC are not exempt from backup withholding: medical and health care payments, attorneys' fees, gross proceeds paid to an attorney reportable under section 6045(f), and payments for services paid by a federal executive agency.

Exemption from FATCA reporting code. The following codes identify payees that are exempt from reporting under FATCA. These codes apply to persons submitting this form for accounts maintained outside of the United States by certain foreign financial institutions. Therefore, if you are only submitting this form for an account you hold in the United States, you may leave this field blank. Consult with the person requesting this form if you are uncertain if the financial institution is subject to these requirements. A requester may indicate that a code is not required by providing you with a Form W-9 with "Not Applicable" (or any similar indication) written or printed on the line for a FATCA exemption code.

A—An organization exempt from tax under section 501(a) or any individual retirement plan as defined in section 7701(a)(37)

B—The United States or any of its agencies or instrumentalities

C—A state, the District of Columbia, a U.S. commonwealth or possession, or any of their political subdivisions or instrumentalities

D—A corporation the stock of which is regularly traded on one or more established securities markets, as described in Regulations section 1.1472-1(c)(1)(i)

E—A corporation that is a member of the same expanded affiliated group as a corporation described in Regulations section 1.1472-1(c)(1)(i)

F—A dealer in securities, commodities, or derivative financial instruments (including notional principal contracts, futures, forwards, and options) that is registered as such under the laws of the United States or any state

G—A real estate investment trust

H—A regulated investment company as defined in section 851 or an entity registered at all times during the tax year under the Investment Company Act of 1940

I—A common trust fund as defined in section 584(a)

J—A bank as defined in section 581

K—A broker

L—A trust exempt from tax under section 664 or described in section 4947(a)(1)

M—A tax exempt trust under a section 403(b) plan or section 457(g) plan

Note: You may wish to consult with the financial institution requesting this form to determine whether the FATCA code and/or exempt payee code should be completed.

Line 5

Enter your address (number, street, and apartment or suite number). This is where the requester of this Form W-9 will mail your information returns. If this address differs from the one the requester already has on file, write NEW at the top. If a new address is provided, there is still a chance the old address will be used until the payor changes your address in their records.

Line 6

Enter your city, state, and ZIP code.

Part I. Taxpayer Identification Number (TIN)

Enter your TIN in the appropriate box. If you are a resident alien and you do not have and are not eligible to get an SSN, your TIN is your IRS individual taxpayer identification number (ITIN). Enter it in the social security number box. If you do not have an ITIN, see *How to get a TIN* below.

If you are a sole proprietor and you have an EIN, you may enter either your SSN or EIN.

If you are a single-member LLC that is disregarded as an entity separate from its owner, enter the owner's SSN (or EIN, if the owner has one). Do not enter the disregarded entity's EIN. If the LLC is classified as a corporation or partnership, enter the entity's EIN.

Note: See *What Name and Number To Give the Requester,* later, for further clarification of name and TIN combinations.

How to get a TIN. If you do not have a TIN, apply for one immediately. To apply for an SSN, get Form SS-5, Application for a Social Security Card, from your local SSA office or get this form online at *www.SSA.gov*. You may also get this form by calling 1-800-772-1213. Use Form W-7, Application for IRS Individual Taxpayer Identification Number, to apply for an ITIN, or Form SS-4, Application for Employer Identification Number, to apply for an EIN. You can apply for an EIN online by accessing the IRS website at *www.irs.gov/Businesses* and clicking on Employer Identification Number (EIN) under Starting a Business. Go to *www.irs.gov/Forms* to view, download, or print Form W-7 and/or Form SS-4. Or, you can go to *www.irs.gov/OrderForms* to place an order and have Form W-7 and/or SS-4 mailed to you within 10 business days.

If you are asked to complete Form W-9 but do not have a TIN, apply for a TIN and write "Applied For" in the space for the TIN, sign and date the form, and give it to the requester. For interest and dividend payments, and certain payments made with respect to readily tradable instruments, generally you will have 60 days to get a TIN and give it to the requester before you are subject to backup withholding on payments. The 60-day rule does not apply to other types of payments. You will be subject to backup withholding on all such payments until you provide your TIN to the requester.

Note: Entering "Applied For" means that you have already applied for a TIN or that you intend to apply for one soon.

Caution: A disregarded U.S. entity that has a foreign owner must use the appropriate Form W-8.

Part II. Certification

To establish to the withholding agent that you are a U.S. person, or resident alien, sign Form W-9. You may be requested to sign by the withholding agent even if item 1, 4, or 5 below indicates otherwise.

For a joint account, only the person whose TIN is shown in Part I should sign (when required). In the case of a disregarded entity, the person identified on line 1 must sign. Exempt payees, see *Exempt payee code,* earlier.

Signature requirements. Complete the certification as indicated in items 1 through 5 below.

1. Interest, dividend, and barter exchange accounts opened before 1984 and broker accounts considered active during 1983. You must give your correct TIN, but you do not have to sign the certification.

2. Interest, dividend, broker, and barter exchange accounts opened after 1983 and broker accounts considered inactive during 1983. You must sign the certification or backup withholding will apply. If you are subject to backup withholding and you are merely providing your correct TIN to the requester, you must cross out item 2 in the certification before signing the form.

3. Real estate transactions. You must sign the certification. You may cross out item 2 of the certification.

4. Other payments. You must give your correct TIN, but you do not have to sign the certification unless you have been notified that you have previously given an incorrect TIN. "Other payments" include payments made in the course of the requester's trade or business for rents, royalties, goods (other than bills for merchandise), medical and health care services (including payments to corporations), payments to a nonemployee for services, payments made in settlement of payment card and third party network transactions, payments to certain fishing boat crew members and fishermen, and gross proceeds paid to attorneys (including payments to corporations).

5. Mortgage interest paid by you, acquisition or abandonment of secured property, cancellation of debt, qualified tuition program payments (under section 529), ABLE accounts (under section 529A), IRA, Coverdell ESA, Archer MSA or HSA contributions or distributions, and pension distributions. You must give your correct TIN, but you do not have to sign the certification.

What Name and Number To Give the Requester

For this type of account:	Give name and SSN of:
1. Individual	The individual
2. Two or more individuals (joint account) other than an account maintained by an FFI	The actual owner of the account or, if combined funds, the first individual on the account[1]
3. Two or more U.S. persons (joint account maintained by an FFI)	Each holder of the account
4. Custodial account of a minor (Uniform Gift to Minors Act)	The minor[2]
5. a. The usual revocable savings trust (grantor is also trustee)	The grantor-trustee[1]
b. So-called trust account that is not a legal or valid trust under state law	The actual owner[1]
6. Sole proprietorship or disregarded entity owned by an individual	The owner[3]
7. Grantor trust filing under Optional Form 1099 Filing Method 1 (see Regulations section 1.671-4(b)(2)(i)(A))	The grantor*
For this type of account:	**Give name and EIN of:**
8. Disregarded entity not owned by an individual	The owner
9. A valid trust, estate, or pension trust	Legal entity[4]
10. Corporation or LLC electing corporate status on Form 8832 or Form 2553	The corporation
11. Association, club, religious, charitable, educational, or other tax-exempt organization	The organization
12. Partnership or multi-member LLC	The partnership
13. A broker or registered nominee	The broker or nominee
14. Account with the Department of Agriculture in the name of a public entity (such as a state or local government, school district, or prison) that receives agricultural program payments	The public entity
15. Grantor trust filing under the Form 1041 Filing Method or the Optional Form 1099 Filing Method 2 (see Regulations section 1.671-4(b)(2)(i)(B))	The trust

[1] List first and circle the name of the person whose number you furnish. If only one person on a joint account has an SSN, that person's number must be furnished.

[2] Circle the minor's name and furnish the minor's SSN.

[3] You must show your individual name and you may also enter your business or DBA name on the "Business name/disregarded entity" name line. You may use either your SSN or EIN (if you have one), but the IRS encourages you to use your SSN.

[4] List first and circle the name of the trust, estate, or pension trust. (Do not furnish the TIN of the personal representative or trustee unless the legal entity itself is not designated in the account title.) Also see *Special rules for partnerships*, earlier.

***Note:** The grantor also must provide a Form W-9 to trustee of trust.

Note: If no name is circled when more than one name is listed, the number will be considered to be that of the first name listed.

Secure Your Tax Records From Identity Theft

Identity theft occurs when someone uses your personal information such as your name, SSN, or other identifying information, without your permission, to commit fraud or other crimes. An identity thief may use your SSN to get a job or may file a tax return using your SSN to receive a refund.

To reduce your risk:

- Protect your SSN,
- Ensure your employer is protecting your SSN, and
- Be careful when choosing a tax preparer.

If your tax records are affected by identity theft and you receive a notice from the IRS, respond right away to the name and phone number printed on the IRS notice or letter.

If your tax records are not currently affected by identity theft but you think you are at risk due to a lost or stolen purse or wallet, questionable credit card activity or credit report, contact the IRS Identity Theft Hotline at 1-800-908-4490 or submit Form 14039.

For more information, see Pub. 5027, Identity Theft Information for Taxpayers.

Victims of identity theft who are experiencing economic harm or a systemic problem, or are seeking help in resolving tax problems that have not been resolved through normal channels, may be eligible for Taxpayer Advocate Service (TAS) assistance. You can reach TAS by calling the TAS toll-free case intake line at 1-877-777-4778 or TTY/TDD 1-800-829-4059.

Protect yourself from suspicious emails or phishing schemes. Phishing is the creation and use of email and websites designed to mimic legitimate business emails and websites. The most common act is sending an email to a user falsely claiming to be an established legitimate enterprise in an attempt to scam the user into surrendering private information that will be used for identity theft.

The IRS does not initiate contacts with taxpayers via emails. Also, the IRS does not request personal detailed information through email or ask taxpayers for the PIN numbers, passwords, or similar secret access information for their credit card, bank, or other financial accounts.

If you receive an unsolicited email claiming to be from the IRS, forward this message to *phishing@irs.gov*. You may also report misuse of the IRS name, logo, or other IRS property to the Treasury Inspector General for Tax Administration (TIGTA) at 1-800-366-4484. You can forward suspicious emails to the Federal Trade Commission at *spam@uce.gov* or report them at *www.ftc.gov/complaint*. You can contact the FTC at *www.ftc.gov/idtheft* or 877-IDTHEFT (877-438-4338). If you have been the victim of identity theft, see *www.IdentityTheft.gov* and Pub. 5027.

Visit *www.irs.gov/IdentityTheft* to learn more about identity theft and how to reduce your risk.

Privacy Act Notice

Section 6109 of the Internal Revenue Code requires you to provide your correct TIN to persons (including federal agencies) who are required to file information returns with the IRS to report interest, dividends, or certain other income paid to you; mortgage interest you paid; the acquisition or abandonment of secured property; the cancellation of debt; or contributions you made to an IRA, Archer MSA, or HSA. The person collecting this form uses the information on the form to file information returns with the IRS, reporting the above information. Routine uses of this information include giving it to the Department of Justice for civil and criminal litigation and to cities, states, the District of Columbia, and U.S. commonwealths and possessions for use in administering their laws. The information also may be disclosed to other countries under a treaty, to federal and state agencies to enforce civil and criminal laws, or to federal law enforcement and intelligence agencies to combat terrorism. You must provide your TIN whether or not you are required to file a tax return. Under section 3406, payers must generally withhold a percentage of taxable interest, dividend, and certain other payments to a payee who does not give a TIN to the payer. Certain penalties may also apply for providing false or fraudulent information.

Woburn Fire Headquarters

WOBURN, MA

DINISCO DESIGN
architects + planners
99 Chauncy Street, Suite 901
Boston, MA 02111
(617) 426-2858

Mitchell Associates Architects PLLC
29 Thacher Park Road
Voorheesville, NY 12186
(518) 765-2950

Brown Sardina, Inc.
Landscape Architects
24 Roland Street
Boston, MA 02129
(617) 482-4703

Horsley Witten Group
Civil & Environmental Engineers
90 Route 6A
Sandwich, MA 02563
(508) 833-6600

Foley Buhl Roberts & Assoc., Inc.
Structural Engineers
2150 Washington Street
Newton, MA 02462
(617) 527-9600

Crabtree McGrath Associates, Inc.
Food Service Consultants
161 West Main Street
Georgetown, MA 01833
(978) 352-8500

VAV International, Inc.
FP, Plumbing, & Mechanical Engineers
400 West Cummings Park, S-4700
Woburn, MA 01801
(781) 935-7228

Thompson Engineering
Electrical Engineers
89 Newbury Street, Suite 103
Danvers, MA 01923
(617) 886-9066

EdVance Technology Design, Inc.
Technology Consultants
300 Brickstone Square, Suite 201
Andover, MA 01880
(978) 256-9900

Hancock Associates
Surveyor
185 Centre Street
Danvers, MA 09123
(978) 777-3050

NORTH ARROW

REGISTERED ARCHITECT RICHARD W. MITCHELL JR. COMMONWEALTH OF MASSACHUSETTS

LICENSE STAMP

Date: 17 MARCH 2021

Drawn By: ADW

Scale: 0 8 16

Revisions

Number	Date	Description

First Floor Plan - Headquarters

SEE DRAWING 6.1.01 FOR FIRE FACILITIES EQUIPMENT

3.4.01

© 2021 DiNisco Design - [30" x 42"] - 5/13/21

Woburn Fire Headquarters

WOBURN, MA



2 **Clerestory Plan**
SCALE: 1/8" = 1'-0"



1 **Training Tower Clerestory Plan**
SCALE: 1/8" = 1'-0"

SEE DRAWING 6.1.01 FOR FIRE FACILITIES EQUIPMENT

DINISCO DESIGN
architects + planners
99 Chauncy Street, Suite 901
Boston, MA 02111
(617) 426-2858

Mitchell Associates Architects PLLC
29 Thacher Park Road
Voorheesville, NY 12186
(518) 765-2950

Brown Sardina, Inc.
Landscape Architects
24 Roland Street
Boston, MA 02129
(617) 482-4703

Horsley Witten Group
Civil & Environmental Engineers
90 Route 6A
Sandwich, MA 02563
(508) 833-6600

Foley Buhl Roberts & Assoc., Inc.
Structural Engineers
2150 Washington Street
Newton, MA 02462
(617) 527-9600

Crabtree McGrath Associates, Inc.
Food Service Consultants
161 West Main Street
Georgetown, MA 01833
(978) 352-8500

VAV International, Inc.
FP, Plumbing, & Mechanical Engineers
400 West Cummings Park, S-4700
Woburn, MA 01801
(781) 935-7228

Thompson Engineering
Electrical Engineers
89 Newbury Street, Suite 103
Danvers, MA 01923
(617) 886-9066

EdVance Technology Design, Inc.
Technology Consultants
300 Brickstone Square, Suite 201
Andover, MA 01880
(978) 256-9900

Hancock Associates
Surveyor
185 Centre Street
Danvers, MA 09123
(978) 777-3050

N
NORTH ARROW

REGISTERED ARCHITECT RICHARD W. DINISCO 20370 COMMONWEALTH OF MASSACHUSETTS
LICENSE STAMP

Date: 17 MARCH 2021

Drawn By: ADW

Scale: 0 8 16

Revisions

Number	Date	Description

Second Floor Plan - Headquarters

3.4.02

© 2021 DiNisco Design - [30" x 42"] - 5/13/21



1 **Support Building First Floor Plan**
SCALE: 1/8" = 1'-0"



2 **Support Building Mezzanine Plan**
SCALE: 1/8" = 1'-0"



3 **Support Building Clerestory Plan**
SCALE: 1/8" = 1'-0"

SEE DRAWING 6.1.01 FOR FIRE FACILITIES EQUIPMENT

Woburn Fire Headquarters

WOBURN, MA

DINISCO DESIGN
architects + planners
99 Chauncy Street, Suite 901
Boston, MA 02111
(617) 426-2858

Mitchell Associates Architects PLLC
29 Thacher Park Road
Voorheesville, NY 12186
(518) 765-2950

Brown Sardina, Inc.
Landscape Architects
24 Roland Street
Boston, MA 02129
(617) 482-4703

Horsley Witten Group
Civil & Environmental Engineers
90 Route 6A
Sandwich, MA 02563
(508) 833-6600

Foley Buhl Roberts & Assoc., Inc.
Structural Engineers
2150 Washington Street
Newton, MA 02462
(617) 527-9600

Crabtree McGrath Associates, Inc.
Food Service Consultants
161 West Main Street
Georgetown, MA 01833
(978) 352-8500

VAV International, Inc.
FP, Plumbing, & Mechanical Engineers
400 West Cummings Park, S-4700
Woburn, MA 01801
(781) 935-7228

Thompson Engineering
Electrical Engineers
89 Newbury Street, Suite 103
Danvers, MA 01923
(617) 886-9066

EdVance Technology Design, Inc.
Technology Consultants
300 Brickstone Square, Suite 201
Andover, MA 01880
(978) 256-9900

Hancock Associates
Surveyor
185 Centre Street
Danvers, MA 09123
(978) 777-3050

NORTH ARROW

REGISTERED ARCHITECT RICHARD M. MICHAUD BOSTON MASS. COMMONWEALTH OF MASSACHUSETTS

LICENSE STAMP

Date: 17 MARCH 2021

Drawn By: ADW, JAO

Scale: 0 8 16

Revisions

Number	Date	Description

Floor Plans - Support Building

3.4.03

© 2021 DiNisco Design - [30" x 42"] - 5/13/21